

Cosmic happenstance: 24- μ m selected, multicomponent *Herschel* sources are line-of-sight projections

Jillian M. Scudder,^{1,2*} Seb Oliver,² Peter D. Hurley,² Julie L. Wardlow,³
Lingyu Wang^{4,5} and Duncan Farrah^{6,7}

¹Department of Physics and Astronomy, Oberlin College, Oberlin, OH 44074, USA

²Astronomy Centre, Department of Physics & Astronomy, University of Sussex, Brighton BN1 9QH, UK

³Centre for Extragalactic Astronomy, Department of Physics, Durham University, South Road, Durham DH1 3LE, UK

⁴SRON Netherlands Institute for Space Research, Landleven 12, NL-9747 AD Groningen, the Netherlands

⁵Kapteyn Astronomical Institute, University of Groningen, Postbus 800, NL-9700 AV Groningen, the Netherlands

⁶Department of Physics and Astronomy, University of Hawaii, 2505 Correa Road, Honolulu, HI 96822, USA

⁷Institute for Astronomy, University of Hawaii, 2680 Woodlawn Drive, Honolulu, HI 96822, USA

Accepted 2018 July 23. Received 2018 July 23; in original form 2018 February 1

ABSTRACT

In this paper, we investigate the physical associations between blended far-infrared (FIR)-emitting galaxies, in order to identify the level of line-of-sight projection contamination in the single-dish *Herschel* data. Building on previous work, and as part of the *Herschel* Extragalactic Legacy Project, we identify a sample of galaxies in the COSMOS field, which are found to be both FIR-bright (typically ~ 15 mJy) and blended within the *Herschel* 250- μ m beam. We identify a spectroscopic or photometric redshift for each FIR-bright source. We conduct a joint probability distribution analysis on the redshift probability density functions to determine the fraction of the FIR sources with multiple FIR-bright counterparts that are likely to be found at consistent ($\Delta z < 0.01$) redshifts. We find that only three (0.4 per cent) of the pair permutations between counterparts are >50 per cent likely to be at consistent redshifts. A majority of counterparts (72 per cent) have no overlap in their redshift probability distributions whatsoever. This is in good agreement with the results of recent simulations, which indicate that single-dish observations of the FIR sky should be strongly contaminated by line-of-sight projection effects. We conclude that for our sample of 3.6- and 24- μ m selected, FIR-bright objects in the COSMOS field, the overwhelming majority of multicomponent FIR systems are line-of-sight projections within the 18.1-arcsec *Herschel* beam, rather than physical associations.

Key words: galaxies: high redshift – galaxies: starburst – galaxies: star formation – galaxies: statistics.

1 INTRODUCTION

As surveys of the galaxy population have evolved, we have become sensitive to an increasingly diverse population of galaxies, and continue to push to higher redshifts. Of particular interest are those galaxy sub-populations that challenge the predictions of theoretical models. The population of luminous galaxies in the far-infrared (FIR) and sub-mm (e.g. Smail, Ivison & Blain 1997; Barger et al. 1998; Hughes et al. 1998) has posed a particular challenge for our current understanding of galaxy evolution.

These galaxies, originally discovered in blind surveys in the sub-mm, have been subjected to a number of follow-up programs, which have determined that these galaxies are typically found at high

redshift (e.g. Smail et al. 2000, 2002; Chapman et al. 2005), and that their luminosity at these wavelengths is due to the presence of large amounts of heated dust. This dust is presumably heated by the presence of significant star formation within the galaxy; the dust is absorbing the UV radiation from massive young stars, and reradiating it at longer wavelengths. For reviews, see Blain (2002) and Casey, Narayanan & Cooray (2014).

These galaxies have posed a significant challenge to theoretical models of galaxy formation, as their luminosity implies astoundingly high star formation rates (SFRs) at very early times in the Universe. Models have invoked a number of potential solutions in order to drive these SFRs, including merger-induced star formation (e.g. Dave et al. 2010; Narayanan et al. 2010), a variable (top-heavy) initial mass function (IMF) (e.g. Baugh et al. 2005), large-scale disc fragmentation (e.g. Immeli et al. 2003), pristine gas infall (e.g. Dekel et al. 2009; Nar 2015), or some combination thereof.

* E-mail: jillian.scudder@oberlin.edu

Testing the theoretical explanations for such elevated SFRs has been challenging, as observations of the sub-mm/FIR luminous galaxy population were historically limited to single-dish facilities with very limited resolution. The typical single-dish facility in the sub-mm has a full width at half-maximum (FWHM) of about 20 arcsec. This low resolution presents several problems, the most severe of which is that it renders accurate counterpart identification at shorter wavelengths (where the resolution is improved) difficult. Within the beam, it is not uncommon to find a number of potential optical counterparts (e.g. Hughes et al. 1998; Richards 1999; Dunlop et al. 2004; Ivison et al. 2007; Clements et al. 2008), and so the identification of the most appropriate counterpart is not straightforward.

This counterpart identification is further complicated by the anticipated difficulty of detecting the FIR flux-emitting galaxy in the optical at all, considering their high redshifts. Because the source of the FIR emission is the joint presence of star formation and large quantities of dust, the counterparts that are most likely to be strongly contributing to the observed sub-mm flux are also likely to be heavily dust-obscured. Much of the optical light will have been absorbed by the very dust that renders them so luminous in the FIR, making the optical colours of these objects extremely red. Furthermore, at the highest redshifts, optical counterparts become increasingly faint. FIR sources, on the other hand, benefit from a negative k -correction, which keeps them visible as bright sources over a very wide redshift range (Blain 2002). For example, a $5 \times 10^{12} L_{\odot}$ galaxy, observed at $\sim 250 \mu\text{m}$, is visible as a $>10\text{-mJy}$ source out to $z \approx 2.5$ (Blain 2002).

In spite of these challenges, for some of the earliest identified sub-mm sources found in regions of the sky with very deep optical data, redshifts were obtained (Hughes et al. 1998; Ivison et al. 1998; Richards 1999; Frayer et al. 2000; Ivison et al. 2000; Chapman et al. 2005). As methods advanced, a number of sub-mm galaxies (SMGs) were successfully targeted with optical telescopes, based on prior radio counterpart identifications (e.g. Ivison et al. 2002). Further observations could map the gas content (typically CO) of a handful of these systems (Frayer et al. 1998, 1999; Ledlow et al. 2002; Neri et al. 2003; Greve et al. 2005; Hainline et al. 2006; Tacconi et al. 2006, 2008). Much of the work on the earliest known sources concluded that due to the clumpy/irregular morphologies or high gas densities, these systems were likely to be late-stage mergers (Ivison et al. 2002; Smail et al. 2003; Tacconi et al. 2006, 2008; Engel et al. 2010; Younger et al. 2010; Zamojski et al. 2011; Menéndez-Delmestre et al. 2013; Wiklind et al. 2014; Chen et al. 2015), though cf. Swinbank et al. (2011), which found evidence for a rotating disc.

This proposed merger-induced origin of sub-mm galaxies was also used to explain the higher than expected levels of clustering found in the SMG population (e.g. Blain et al. 2004; Farrah et al. 2006; Amblard et al. 2011; Cowley et al. 2016). Studies also found that there were a higher than expected number of radio counterparts in close proximity to FIR sources; a statistical argument was made arguing for the unlikelihood of this arrangement at random (Ivison et al. 2007). Merger-induced star formation, which had been predicted by some theoretical models (e.g. Baugh et al. 2005; Swinbank et al. 2008; Dekel et al. 2009; Dave et al. 2010; Narayanan et al. 2010), could be invoked to explain the unusually high levels of star formation (e.g. Rowan-Robinson et al. 2017) within these systems. A detailed discussion of the origins of this merger-induced model of sub-mm galaxies is undertaken in Appendices A and B.

As sub-mm interferometric facilities, such as ALMA, have come online, we have begun to observe these sources at much higher

resolution without needing to change wavelengths. High-resolution studies have typically found that some sub-mm sources tend to divide into a number of FIR-bright components (Hodge et al. 2013a; Karim et al. 2013; Simpson et al. 2017; Trakhtenbrot et al. 2017). In these cases, the SFRs previously attributed to a single galaxy should be divided amongst multiple components, reducing the extremity of star formation in each individual object, though if these objects are interacting, the SFR of the system remains elevated. Scudder et al. (2016) similarly found that single-dish FIR sources are also best reproduced by multiple FIR-bright components, using a statistical method (Hurley et al. 2017).

The interpretation of the single-dish flux therefore remains unclear. If these counterparts are all at the same redshift, the unresolved FIR flux traces the SFR of a physical system instead of a single galaxy. However, the theoretical challenge remains if the components are physically associated. If these multiple components are all part of interactions, theoretical models must still produce starbursts at early times in order to replicate the observations, which continue to be a significant challenge. Alternately, if these multiple components are physically unrelated, appearing close on the sky by virtue of line-of-sight projection effects and a broad range of redshift visibilities, then the theoretical models do not need to strain as hard to produce massive bursts of star formation in the very early Universe. Indeed, Efstathiou & Rowan-Robinson (2003) predicted that many of these observed sub-mm galaxies may be closer to normal star-forming galaxies than extreme starbursts. Secular disc fragmentation, also suggested as a pathway to generate sub-mm galaxies (e.g. Immeli et al. 2003; Bournaud & Elmegreen 2009; Dekel et al. 2009) may be a viable explanation for the irregular morphologies observed.

As theoretical models become more complex, simulations have begun to assess the frequency of single-dish observations blending sources together. A number of simulations now suggest that source blending should be significant, both for physically associated galaxies (Hayward et al. 2012) and for galaxies, which are entirely unrelated (Hayward et al. 2011, 2013; Cowley et al. 2014; Muñoz Arancibia et al. 2014; Cowley et al. 2016; Béthermin et al. 2017). The fraction of totally unrelated sources varies between simulations, but has been estimated to be in the range of 50 per cent to as high as 70 per cent (Hayward et al. 2013; Cowley et al. 2014; Béthermin et al. 2017).

In this work, we build upon previous work that identified a sample of FIR-bright counterparts to a sample of *Herschel* sources in the COSMOS field (Scudder et al. 2016). We identify the spectroscopic or photometric redshifts associated with these FIR luminous counterparts and test directly, on a statistical sample, whether these multiple component systems are likely to be physically associated or are simply line-of-sight projections. The results of this work will give a framework for understanding the meaning of an FIR blended source more broadly.

In Section 2, we describe the selection of our FIR-bright counterpart sample. In Section 3, we describe our data analysis. In Section 4, we discuss the implications of our work in the context of the literature. In Section 5, we present our conclusions. The full set of figures for all FIR sources within our sample is available online.¹ Throughout this work, we assume *WMAP* 9 cosmology (Hinshaw et al. 2013).²

¹Figures are available at <https://github.com/jmscudder/Redshift-figs>

²This cosmology is $\Omega_M = 0.282$, $\Omega_{\Lambda} = 0.718$, $H_0 = 69.7 \text{ km s}^{-1} \text{ Mpc}^{-1}$

Table 1. A summary of the data used in this work.

Wavelength	Flux density limit	Facility	Data source
250 μm	≥ 30 mJy	<i>Herschel</i>	Levenson et al. (2010) Wang et al. (2014)
24 μm	≥ 50 μJy	<i>Spitzer</i>	Le Flocc'h et al. (2009)
3.6 μm	≥ 0.9 μJy	<i>Spitzer</i>	Sanders et al. (2007)

2 SAMPLE SELECTION

In this work, we build upon the work of Scudder et al. (2016), and use the sample defined therein. For a full description of the sample selection, we refer the reader to that work. For clarity, we also provide a brief description of our selection criteria here.

2.1 The Scudder et al. (2016) sample

Scudder et al. (2016) define their sample within the COSMOS field region (Scoville et al. 2007) because of the strong multiwavelength coverage in that field. In particular, Scudder et al. (2016) make use of the 250- μm coverage of the COSMOS region by the Spectral and Photometric Imaging Receiver (Griffin et al. 2010) instrument on-board the *Herschel Space Observatory* (Pilbratt et al. 2010). These observations were part of the *Herschel* Multitiered Extragalactic Survey (Roseboom et al. 2010). Scudder et al. (2016) also made use of pre-existing 3.6- and 24- μm catalogues in this field. We summarize the data used in Table 1.

Each 250- μm source above a flux density threshold of 30 mJy was cross-matched with the 3.6- and 24- μm catalogues. FIR sources were preserved in the sample if they had ≥ 1 detection at 3.6 and 24 μm within 18.1 arcsec (the FWHM of *Herschel* at this wavelength) of the 250- μm catalogue position. The 3.6- and 24- μm wavelength detections were permitted to spatially overlap, and there was no requirement for >1 detection in each band. Scudder et al. (2016) identified 360 such FIR sources, with a median number of 14 possible multiwavelength (3.6- and/or 24- μm) counterparts³ per 250- μm detection.

The $\text{xID}+$ software (Hurley et al. 2017) was used to identify the most probable distribution of FIR flux amongst these potential counterparts. The methodology and tests of this tool on simulated data are fully explored in Hurley et al. (2017). Briefly, $\text{xID}+$ is a Bayesian inference tool that uses the positions⁴ of known objects to determine the most likely distribution of flux between those known objects, so that the input map (in this case, the 250- μm map) is best reproduced. Hurley et al. (2017) show that $\text{xID}+$ both accurately recovers fluxes in a synthetic map of the COSMOS region, and produces accurate estimations of its errors. As the output of $\text{xID}+$ is a full posterior distribution function, any non-Gaussianities in the flux solutions, or strong degeneracies between solutions (e.g. in the case that two sources are too close together for the software to provide a preferred solution) are preserved. The full set of flux solutions and correlations between sources for the Scudder et al. (2016) sample

³A point of linguistic clarity: in this work, we refer to the FIR detection as the ‘object’ or ‘source’, with the positions of the higher resolution 3.6- and 24- μm detections as ‘counterparts’ to the FIR detection.

⁴In this iteration of $\text{xID}+$, the only prior information used is that of the positions. The software is under active development (available at https://github.com/H-E-L-P/XID_plus) and the ability to use flux priors will soon be available.

is available online.⁵ In Scudder et al. (2016), all known 3.6- μm sources within a 180 arcsec \times 180 arcsec region surrounding each FIR source of interest are used in the fitting procedure, in order to avoid poor fits due to other bright sources near the FIR source of interest.

2.2 The FIR-bright subsample

In this work, we are interested in investigating the redshifts of the FIR-bright population. As the $\text{xID}+$ analysis provides a full probability density function (PDF) of possible flux solutions, defining a level of FIR-brightness is somewhat arbitrary. An absolute flux threshold preferentially selects counterparts from brighter FIR sources, so to avoid this bias, we use the fraction of the total FIR flux assigned to a given component as a more scalable method of selecting sources that significantly contribute to the FIR flux observed in the map. For each $\text{xID}+$ flux solution, we calculate the flux ratio of a given counterpart relative to the sum of all contributing sources. This builds up a PDF for the flux ratios. Any counterparts that have a median flux ratio greater than 10 per cent are flagged as significantly contributing (henceforth FIR-bright).

We note that for very low flux (\sim few mJy) solutions, the final PDF of flux solutions is strongly non-Gaussian, and the median is not a good estimator of the typical flux solution. However, once the flux solutions rise above a few mJy, the median is typically a good estimator of the flux solution distribution (Hurley et al. 2017). In Scudder et al. (2016), we chose a threshold of 10 per cent of the total flux as the limit for significantly contributing. For consistency, we retain that definition in this work. As our lowest FIR flux source is 30 mJy, the smallest possible flux that could pass the 10 per cent threshold is 3 mJy. The median flux in our FIR-bright counterpart sample is ~ 15 mJy, with very few (2.6 per cent) components with fluxes < 5 mJy. Our median values should therefore be reliable estimators of the posterior distribution. As above, the complete set of figures that show median estimates of all flux solutions from Scudder et al. (2016) is available online.

In Fig. 1, we show a histogram of the number of FIR-bright components per FIR object for the full sample of 360 FIR objects from Scudder et al. (2016). Along the left vertical axis, we show the fraction of the 360 FIR objects that have the given number of bright counterparts; on the right, we translate this into a raw number of FIR objects. As reported in Scudder et al. (2016), the vast majority of FIR objects have more than one bright component. However, approximately 7 per cent (26 individual objects) of the 360 FIR objects are comprised of a single component only. These single-component objects are those FIR detections that are best explained via a single luminous counterpart.

We wish to examine the redshifts of the objects that are blends of multiple FIR-bright components, and so we exclude these single-counterpart objects for the remainder of this work. However, we note that since these objects do not make up a significant fraction of the overall sample, this is not a major reduction in sample size.⁶ Once this criterion has been put in place, our sample contains 334 FIR objects with more than one bright counterpart, with a total of 935 FIR-bright counterparts within these fields.

⁵Flux solutions and intercorrelation figures are available for the 360 FIR sources at <http://jmscudder.github.io/XID-figures>

⁶The exclusion of these 26 objects may influence mean statistics, though we emphasize the small number of sources.




Figure 1. A histogram showing the number of FIR-bright counterparts per FIR source, per the `xid+` analysis. FIR-bright is defined as a counterpart that contributes >10 per cent of the total FIR flux. The left-hand vertical axis shows the fraction of the total sample in each bin, and the right-hand vertical axis gives this value as a number of FIR objects. The majority of FIR sources have two to three FIR-bright counterparts.

Table 2. A summary of the quality control flags imposed on the spectroscopic and photometric redshift catalogues.

Photometric catalogue	Spectroscopic catalogue
$z > 0$	$z > 0$
$\text{STAR_FLAG} = <1$	$Z_USE < 3$

2.3 Redshift identification

We now identify the redshift of each FIR-bright counterpart. The COSMOS field benefits from extensive spectroscopic and photometric redshift availability. We use the Davies et al. (2014) catalogue of spectroscopic redshifts, which collects and reprocesses the zCOSMOS spectra (Lilly et al. 2009), along with spectra from VVDS (Le Fevre et al. 2013), PRIMUS (Cool et al. 2013), and SDSS (Ahn et al. 2014).

For photometric redshifts, we use the Laigle et al. (2016) catalogue of photometric redshifts. The Laigle et al. (2016) photometric catalogue is extremely well calibrated to spectroscopic redshifts, and has a precision relative to the COSMOS spectroscopic catalogue (Lilly et al. 2009) of $\frac{|z_p - z_s|}{1+z_s} = 0.007$, with a catastrophic failure rate of 0.5 per cent (Laigle et al. 2016). Above a redshift of 3, the Laigle et al. (2016) catalogue maintains a redshift precision of $\frac{|z_p - z_s|}{1+z_s} = 0.021$, with a failure rate of 13.2 per cent.

We implement basic quality filters on the Laigle et al. (2016) catalogue and on our spectroscopic catalogue from Davies et al. (2014), which are summarized in Table 2. We require that any redshift solution is above zero ($z > 0$). The photometric catalogue is additionally required to be outside of a star mask region, $\text{STAR_FLAG} = <1$. This combination of flags is similar to the recommended quality flag $\text{FLAG_PETER} = 0$, but not identical, as a number of our sources lie outside the main COSMOS region, which is masked by both $\text{FLAG_COSMOS} = 1$ and

Table 3. Description of the distribution of redshift identifications. The top rows indicate the number of total FIR-bright components, and the number of those components that had identifiable redshifts. The bottom rows subdivide the counterparts that were missing redshifts.

Total components:	935
Counterparts with identified redshifts:	806
Counterparts without redshifts:	129
0 counterpart redshifts remaining per FIR object:	37/129
1 counterpart redshift remaining per FIR object:	49/129
≥ 2 counterpart redshifts remaining per FIR object:	43/129

$\text{FLAG_PETER} = 0$. We also require $z_USE < 3$, which limits the spectroscopic redshifts to either high-resolution spectra (e.g. from zCOSMOS) or where reliable redshifts were estimated from PRIMUS (Davies et al. 2014).

In order to identify the redshift associated with each of our counterparts, we search a 2-arcsec radius surrounding the shorter wavelength (3.6- or 24- μm) counterpart location, and identify the nearest spectroscopic redshift and the nearest photometric redshift to that. In the vast majority of cases, only one redshift type exists, and that redshift, be it spectroscopic or photometric, is accepted as the redshift of the shorter wavelength counterpart. In the case where both spectroscopic and photometric redshifts exist, the closer spatial identification is accepted.

If there are no spectroscopic or photometric redshift matches within 2 arcsec, the FIR-bright counterpart is flagged as having no identifiable redshift, and excluded from the analysis that follows. Some FIR objects have no redshifts for any of their 3.6- or 24- μm counterparts. We determined that the vast majority of the redshift identification failures are due to contamination of the optical imaging by the presence of a bright star. The bright star flux renders the optical imaging sufficiently unreliable that photometric redshifts were not calculated.

If all counterparts for a given FIR object fail the redshift identification process (true for 16/334 of our FIR objects, or 4.8 per cent), the FIR object is excluded from the analysis that follows. In some cases, only one counterpart associated with an FIR object has a redshift. In this case, no pairwise redshift comparison can be undertaken and the FIR object must be discarded from our analysis. As long as there remains >1 counterpart with a redshift identified, the FIR object is preserved in the analysis. We discuss the possible impact of this loss of individual counterparts to the results of our analysis in Section 4, but find that this should not significantly affect the results presented here.

806 of 935 counterparts have redshift identifications (86 per cent). We break down the redshift identification results in Table 3. Of those that are missing, 37 counterparts are associated with one of the 16 FIR objects that have no redshift identifications at all. These blank regions reduce our FIR object count from 334 to 318. The remaining 92 redshift-unidentified counterparts have at least one other redshift within the field. 49 of the 92 unmatched counterparts have only one counterpart with a redshift identifications associated with a specific FIR source, which results in the loss of 38 FIR fields (along with 38 redshift identifications) from our analysis. Our final sample contains 280 FIR objects, with 768 associated counterparts, which have had ≥ 2 redshifts successfully identified. 95 (12.4 per cent) of the final sample has spectroscopic redshifts; 673 (87.6 per cent) counterparts have photometric redshifts.




Figure 2. The redshift probability distribution functions of two sample FIR sources, with three FIR-bright counterparts each. Very broad distributions indicate less well-confined photometric redshift distributions, whereas narrow peaks indicate spectroscopic observations or (as here) very good photometric redshift solutions. The cumulative probability has been normalized to 1. We calculate the joint probability distribution for all combinations of pairs in these systems. In these cases, there are three unique permutations: [purple dashed]–[blue solid], [purple dashed]–[orange dot–dashed], and [orange dot–dashed]–[blue solid]. The top panel shows ID 3422. The redshift PDFs do not overlap within a tolerance of $z = 0.01$. In the bottom panel, we show ID 9007, where there is significant overlap between the PDFs.

3 ANALYSIS

We make use of the full photometric PDFs, which are discretized in redshift bins⁷ of $\Delta z = 0.01$, from the Laigle et al. (2016) catalogue for all counterparts with photometric redshifts. We renormalize the redshift PDFs such that the cumulative probability is equal to 1. If a source has been matched to a spectroscopic redshift, we assume that its PDF has 100 per cent probability of being found within a single $\Delta z = 0.01$ redshift bin. In Fig. 2, we show the PDFs of the redshifts for two randomly selected FIR sources (ID 3422, top panel; ID 9007, bottom panel). 3422 has one counterpart with a very

⁷At a redshift of 1.0, the median of our sample, $\Delta z = 0.01$ corresponds to a change in luminosity distance of ~ 83 Mpc. $\Delta z = 0.05$ corresponds to ~ 415 Mpc.

well-constrained photometric PDF at $z = 0.3$, plotted in a dashed purple line, which has non-zero probability contained within two $\Delta z = 0.01$ bins. The other two counterparts’ redshifts have much broader PDFs. In the bottom panel, we show an example where the counterparts’ redshift PDFs are found to be in overlap. Here, we have three moderately well-constrained PDFs, with the counterpart plotted in orange dot–dashed in overlap with both other counterpart PDFs. All other fields with redshift identifications for more than one component are available online.⁸ Unless otherwise specified, we retain the discretization in redshift space at $\Delta z = 0.01$. We note that while this discretization is smaller than the typical error at $z > 3.0$, the fraction of our sources that are found above a redshift of 3.0 is small, and we have repeated our analysis with larger Δz bin sizes and find our results are broadly unchanged.

3.1 The redshift distribution of the FIR-bright sample

We first wish to determine whether there is any systematic difference in the redshift distribution of the FIR-bright counterparts and the COSMOS photometric catalogue from which it was drawn. We therefore build up the cumulative probability distribution across all FIR-bright counterparts, effectively summing the counterpart PDFs shown in Fig. 2 across all FIR-bright counterparts, described by

$$P(z) = \sum_{c=0}^c (P_c(z)), \quad (1)$$

where z is a given redshift solution, $P(z)$ is the cumulative probability density at a given redshift, c is an index ranging from 0 to 752 (the number of counterparts), and $P_c(z)$ is the probability density for a given counterpart at the given redshift. The result of this operation⁹ is shown as the purple solid line in Fig. 3, normalized so that the sum of the probability density is equal to 1. For clarity, in this figure we have expanded the bins to $\Delta z = 0.15$.

To compare to the COSMOS sample, we randomly draw 5000 galaxies from the quality-controlled COSMOS photometric catalogue, and compute their cumulative probability distributions in the same way. The only change to equation (1) is that c now ranges from 0 to 5000. The cumulative PDF for the random sampling is shown as the red dashed line in Fig. 3. It is immediately clear that while both samples cover a broad range of redshift space, the FIR-bright sample is more tightly clustered around a redshift of 1.0 than the randomly selected sample. The randomly selected photometric sources, by contrast, have a stronger tail out to both lower and higher redshifts. This peak at $z = 1.0$ in the FIR-bright sample is not surprising, as it has been found that the 24- μm selected, 250- μm *Herschel* sources (similar to the selection in this work) have a peak in their redshift distribution around this value, with previous work reporting the peak between $z = 0.85$ (Casey et al. 2012) and $z \sim 1.0$ (B  thermin et al. 2012). Surveys selected at longer wavelengths, for instance an 850- μm selection, typically peak at a redshift of $z \approx 2.5$ (e.g. Chapman et al. 2005; Casey et al. 2012).

We plot the ratio between the two samples ($\frac{FIR\text{-}bright}{random}$) in the bottom panel of Fig. 3 in a dashed red line. This ratio shows the relative excess or deficiency in probability that an FIR-bright counterpart is found at a specific redshift, compared to the randomly selected sample, and more clearly demonstrates the differences between the two

⁸These figures are available online at <https://github.com/jmscudder/Redshift-figs>

⁹This analysis assumes that all PDFs within the Laigle et al. (2016) catalogue are independent of each other.




Figure 3. The summed redshift probability for *all* FIR-bright sources across all FIR objects, plotted as the purple solid line. We have expanded the bins to $\Delta z = 0.15$. In a red dashed line, we show a random sampling of 5000 redshifts from the photometric redshift catalogue. We see that both redshift distributions largely span the same range, but the COSMOS catalogue is less peaked at redshifts of $0.4 < z < 1.5$, and has a stronger tail to high redshifts. In the lower panel, we plot the ratio between the two curves: $\left(\frac{FIR\text{-}bright}{random}\right)$ at each z . This ratio shows explicitly the excess of probability in the FIR sample in the redshift range $0.4 < z < 1.5$.

histograms. The FIR-bright counterpart sample is underrepresented at all redshifts relative to the COSMOS photometric catalogue except between redshifts of $0.4 \lesssim z \lesssim 2.0$. The peak of the FIR-bright sample at $z \approx 1.0$ can be seen as an excess of probability density of 1.5 times the random COSMOS catalogue.

3.2 Δ Mpc probability function

We wish to estimate the redshift difference between FIR-bright components contributing to a given FIR object without losing valuable information from the PDFs. As Fig. 2 illustrates, the width of the redshift PDFs can vary significantly, and the broadest redshift solutions are not always well described by their medians. We must therefore estimate both the range in possible redshift differences (Δz), and the likelihood of each possible value of Δz . In order to address the large redshift ranges probed by this calculation, we convert redshift to a comoving distance.

For each FIR source, we identify all pair permutations between counterparts. In Fig. 2, we have three unique pair permutations: [blue dashed]–[purple solid], [blue dashed]–[green dot-dashed], and [green dot-dashed]–[purple solid]. For a given pairing, we denote the PDFs of the two counterparts as P_a and P_b . We select the regions of redshift space over which $P(z) > 0$, and convert the remaining redshifts into comoving distances. For each permitted comoving distance solution, D_a , in P_a , we subtract all possible distance solutions, D_b , in P_b . We store the absolute value of the difference: $\Delta D_{ab} = |D_a - D_b|$.

In order to retain the probability information, for each Δ Mpc solution we weight by the probability of the two distance solutions D_a and D_b , described by

$$P(\Delta \text{Mpc} = \Delta D_{ab}) = P_a(D_a) \times P_b(D_b). \quad (2)$$

Duplicate Δ Mpc values (of which there should be many, as adjacent bins provide similar Δ Mpc) have their probabilities summed




Figure 4. All possible solutions for Δ Mpc, weighted by their probability, for the same set of counterparts as Fig. 2. In the top panel we again show ID 3422, and in the bottom panel, ID 9007. For each unique pair of counterparts, we calculate all possible differences in comoving distance between it and the other bright components, given the range of solutions in the PDF. We then weight the differences by the likelihood of the redshift solutions $P(z)$. The shape of the original PDFs is reflected in the top panel, though somewhat horizontally compressed due to the conversion into Mpc that has been applied. In the bottom panel, we do not see the same distinct peaks, as the original PDFs are significantly in overlap. The cumulative probability in these figures sums to the number of counterparts (i.e. 3.0 for both panels).

together for the final analysis. Once all Δ Mpc and $P(\Delta \text{Mpc} = \Delta D_{ab})$ values have been determined for a given pair, this process is repeated for all pair permutations that exist for that FIR object. We demonstrate the output of this method by showing the results for ID 3422 and ID 9007 in the top and bottom panels of Fig. 4, respectively. The full set of these figures for all FIR objects is also available online.¹⁰

In the top panel, the shapes of the original PDFs are reflected in the shape of the histogram. The stronger peak at $\Delta \text{Mpc} = 5000$ reflects the difference between the purple dashed and orange dot-dashed PDFs in the top panel of Fig. 2. The middle peak reflects the differences between the purple dashed and blue solid peaks,

¹⁰<https://github.com/jmscudder/Redshift-figs>




Figure 5. The probability of any two pairs being separated by a given ΔMpc . In black, we show the distribution of ΔMpc across all 281 FIR sources with more than one bright counterpart (FIR-bright). In dashed purple, we show the results of a random resampling of the FIR-bright sample. From the FIR-bright sample, we randomly select 280 sets of 3 counterparts, which will not be physically associated. We calculate their ΔMpc , and perform a KS test on the resampled and the FIR-bright sample to determine if the null hypothesis that the two samples are drawn from the same parent distribution can be excluded. This process is repeated 1000 times. We show the median KS test p -value in the top corner: 0.644. The purple dashed curve shows the normalized results of all 1000 resamplings. These curves have been normalized so that the cumulative probability sums to 1.0.

and the leftmost peak reflects the difference between the blue solid and orange dot-dashed peaks in Fig. 2. In the bottom panel, we see a much broader distribution of ΔMpc values for ID 9007. As the original PDFs were much more strongly in overlap, a continuous distribution of ΔMpc values is to be expected.

As with Fig. 3, in Fig. 5 we show the cumulative ΔMpc histogram. This histogram illustrates the difference, in Mpc, along the line of sight for our FIR-bright sample of counterparts. For each ΔMpc value, we find the sum of the probabilities across all FIR objects that found ΔMpc as a solution. Fig. 5 therefore illustrates the probability of any two pairs in our FIR-bright sample to be found at a specific ΔMpc . We aim to determine if there is a preferential clustering among the FIR-bright sample. However, comparing to the COSMOS photometric catalogue will be difficult, as we have shown in Fig. 3 that the redshift distributions are different in the two samples, and we will be more likely to find counterparts at smaller ΔMpc separations simply because the redshift peak for the FIR-bright sample is narrow.

We therefore test for preferential clustering in the FIR-bright sample by randomly resampling from the FIR-bright sample itself. If there is a preference for small ΔMpc solutions in the data, randomly resampling should remove it. We therefore assemble all counterpart PDFs, and randomly sample sets of three PDFs. We then calculate the ΔMpc values for these three. This is repeated 280 times to replicate the size of the FIR-bright sample, and a cumulative histogram is generated in the same way as for the FIR-bright sample. We use a Kolmogorov–Smirnov (KS) test on the cumulative histograms to assess if the null hypothesis, that the two samples are drawn from the same parent population, can be excluded. We then repeat this random resampling process 1000 times, and perform the KS test for each resampling. We are unable to exclude the null hypothesis at $>3\sigma$ in 100 per cent of our tests. The median KS test p -val is 0.644.

We interpret this to mean that we are not seeing a statistically significant preferential clustering signal within the FIR-bright sample, and that our data are consistent with being drawn randomly from the FIR-bright redshift distribution shown in Fig. 3.

3.3 Probability of consistent redshift

Thus far, we have focused on the distinctness of the FIR-bright population as a whole, and found that averaged over all of our FIR sources, the contributing counterparts are found to be part of a redshift distribution that is strongly peaked at a redshift of ~ 1 . However, we have not yet tackled the key question of whether the counterparts that contribute to a specific FIR detection are likely to be physically associated, i.e. if they are at the *same* redshift.

We define ‘consistent redshift’ as existing within the same redshift bin, which, due to the SED fitting procedure, has a minimum redshift gridding of $\Delta z = 0.01$. We use the full probability density function to construct a joint probability distribution between all combinations of counterparts associated with a given FIR object, using a methodology described by equation (3) below.

$$P(z_a=z_b) = \sum_z P_a(z) \times P_b(z). \quad (3)$$

For each pair of FIR-bright components (a and b), we multiply their probabilities [$P_a(z)$ and $P_b(z)$] of existing at a given redshift (z), and sum across all redshift solutions. This produces the overall joint probability distribution $P(z_a = z_b)$, which is the likelihood that the redshift solutions for components a and b are within the same redshift bin. With a larger overlap in the PDFs, or a higher probability of a given redshift solution in the overlapping region, the likelihood that components a and b are found at consistent redshifts increases.

This calculation is used to assess the plausibility of physical association for any two component pairs blended beneath a given FIR object. If the joint probability is very low (or zero), then there is very little (or no) chance that the two components are physically associated, but rather are line-of-sight projections near to each other on the sky.¹¹

If there is no overlap in the PDF solutions at any redshift, the joint probability is 0. This is the case for the PDFs presented in the top panel of Fig. 2; all pairs of components have 0 probability of being found within $\Delta z = 0.01$. At the other extreme, if two spectroscopic redshifts are present within the same $\Delta z = 0.01$ bin, the joint probability distribution would indicate that pair has a very high (100 per cent) probability of being found at a consistent redshift. These sources are *potentially* physically associated, and could be in the early stages of a merger. However, we note that at a redshift of 1.0, a Δz of 0.01 is still probing ~ 80 Mpc, and so even sources that are found with extremely high probability of being at a consistent redshift are not guaranteed to be physically associated.

We compute the joint probability of all 736 counterpart pair permutations, for all fields in which there are ≥ 2 bright components with redshifts. We plot a histogram of the resultant probabilities in the top left panel of Fig. 6. Three pair combinations (0.4 per cent) are found to have more than 50 per cent probability of being at

¹¹We have tested an alternative method of convolving the two redshift probability density functions using test Gaussian distributions. We find that integrating the probability distribution of $z_a - z_b$, created by convolving the two test distributions, between $\pm \Delta z$ is equivalent to equation (3) so long as the sampling and normalization are done consistently. As equation (3) is a simpler calculation we proceed with the methodology described above.




Figure 6. The probability of any two component pairs being found within our tested redshift tolerances, $\Delta z < 0.01, 0.05, 0.08,$ and 0.1 . This figure reflects the distribution of Δz across all 280 FIR sources with more than one bright, redshift-matched, counterpart (736 counterpart pair combinations). The black dotted vertical line indicates 50 per cent probability. The top left panel shows our fiducial value, of $\Delta z = 0.01$. The vast majority (99.6 per cent in this case) of FIR sources do not have multiple contributing sources at a consistent redshift. Three pairs are found with >50 per cent probability of being found at the same redshift, while 536 pairs have 0 per cent probability of being found at the same redshift. In the top right panel, we expand our redshift tolerance to $\Delta z = 0.05$, and find 14 (1.9 per cent) plausibly consistent pairs, and 524 (71.2 per cent) counterparts that remain at zero probability of being at a consistent redshift. In the lower left and right panels, we show $\Delta z = 0.08$ and $\Delta z = 0.1$, respectively. Even at these much larger redshift tolerances, the consistent pair fraction remains very low, at 3.7 per cent and 4.2 per cent, respectively.

a consistent redshift. The remainder of the sources all have lower probabilities, with the vast majority of the sample found to have no overlap in the PDFs whatsoever. The median value for this histogram is 0, and 536 pair combinations (72.8 per cent) have this value. This distribution indicates that the vast majority of our sample is not comprised of physical pairs.

Because of the discrete nature of the PDFs, it is possible that two counterparts lie within $\Delta z = 0.01$, but are classed in adjacent bins. This would artificially lower their joint probability. To account for this potential problem, we have repeated this analysis with broader redshift tolerances ($\Delta z = 0.05, \Delta z = 0.08,$ and $\Delta z = 0.1$). By increasing the redshift bin size, we should capture those counterparts that are close in redshift but not placed in the same bin. We

find that this does not significantly alter our results. The results for these additional three tolerance thresholds are plotted in Fig. 6. The $\Delta z = 0.05$ bin width (top right panel) results in 14 consistent pairings, or 1.90 per cent. A $\Delta z = 0.08$ bin width (bottom left panel) results in a consistency fraction of 3.67 per cent, and $\Delta z = 0.1$ (bottom right panel) results in a consistent redshift fraction of 4.21 per cent of the sample. The fraction of the sample at a joint probability value of zero remains very high as the redshift bin width increases, which indicates that our data analysis is not substantially affected by well-constrained redshift PDFs in adjacent redshift bins.

We note that we do not expect redshift uncertainties to dramatically alter these results, as the width of the photometric redshift

PDFs is taken into account by equation (3). If the width of the photometric redshift PDFs is underestimated, then these estimates could also be underestimated, however, by artificially increasing the bin size, we have accounted for galaxies that could be within a Δz range of up to 0.1 (many hundreds of Mpc). Increasing the bin size will only affect those galaxies with slightly overlapping PDFs or well-constrained PDFs that are very close in redshift; for those galaxies with PDFs that have very different redshift solutions (i.e. those galaxies with 0 probability density in common), increasing coarseness of the PDF by a factor of 10 will not impact the results presented here.

4 DISCUSSION

Our results show that the vast majority of the blended FIR-bright counterparts to 24- and 3.6- μm -selected FIR objects are physically unrelated. A significant portion of our FIR-bright counterparts have no overlap in their redshift PDFs whatsoever, and appear to be consistent with being drawn randomly from the redshift distribution of our FIR-bright sample. Given the longstanding debate on the merger origin of these FIR objects, these results may seem surprising. While the results presented here do not rule out the existence of FIR-bright pairs or mergers in some fraction of the sub-mm population, we suggest that those pairs are not a significant fraction of the 24- μm -selected sub-mm population.¹² We note that this study is fundamentally limited by the resolution of the IRAC 3.6- μm FWHM (2 arcsec), and so any interactions at the final stages of a merger will be unresolved. We are furthermore insensitive to any interactions where the companion is FIR faint or very low mass. However, in low-redshift studies, equal mass encounters are responsible for the strongest starbursts (e.g. Woods & Geller 2007; Scudder et al. 2012) and these encounters typically result in roughly symmetric responses in both galaxies (e.g. Scudder et al. 2012; Torrey et al. 2012). We discuss the resolution limitation further below.

It is possible that during our redshift identification phase, due to the incompleteness of the redshift matching, we have excluded physical pairs from our analysis. To quantify the extent to which this could affect our results, we estimate how strongly this exclusion could bias the numbers we present here. Our sample has excluded 129 counterparts that did not have available redshifts (see Table 3). We subdivide the sample that is missing redshifts by the number of remaining counterparts that did have redshifts, for that same FIR object. The 37 counterparts that had no redshifts remaining triggered the exclusion of 16 of FIR objects from our analysis. It is unlikely that any bias comes from these missing FIR objects, as no redshifts were preferentially excluded. However, there was a population of 92 counterparts that were unmatched, for FIR objects with some identified redshifts.

These 92 counterparts represent 11 per cent of the FIR-bright sample. For the 49 counterparts that left only one redshift identification associated with a given FIR object, the failure to match reduced the FIR object count by 38. If we assume that all 38 of the missing FIR objects contained a consistent redshift, and that all 43 of the missing counterparts that did not remove the field from the sample would have given a consistent redshift to one of the remaining counterparts, we can estimate how much our redshift incompleteness could change our results. If we increase the total

number of consistent pairs (at >50 per cent) from 3 to 84, and the number of total counterpart combinations from 736 to 817, we find that our consistency fraction only increases to 10.2 per cent from our fiducial value of 0.4 per cent. We note that assuming all of the missing redshifts would have produced a consistent redshift is extremely unlikely, given the distribution shown in Fig. 6, and we expect the true value to be lower. Even with these conservative adjustments, it is safe to say that the overwhelming majority of the FIR-bright objects are not physically associated.

We also check for AGN contamination in the sample, as Marchesi et al. (2016) showed that the photometric redshifts can be significantly shifted if a strong AGN is present and not accounted for. We cross-match with the Marchesi et al. (2016) sample and find that only 18 of our 768 FIR-bright counterparts are within their sample (2.3 per cent). Replacing the PDFs presented here with those calculated with an AGN template does not change the fraction of pairs with >50 per cent likelihood of existing at the redshift. At least in this sample, accounting for AGN does not influence these results.

These results mesh extremely well with the newest generation of simulations, which have been treating observational biases more robustly. As an increasing number of interferometric results have begun to challenge the assumption that the single-dish data are flux coming from a single galaxy (e.g. Hodge et al. 2013a; Karim et al. 2013; Simpson et al. 2015), simulations are well placed to determine if multiple component systems are likely to be physically interacting or rather are a consequence of projection effects. The current theoretical consensus seems to be that the vast majority of the sub-mm bright sources that are comprised of multiple components should be made up of unrelated components (Hayward et al. 2013; Cowley et al. 2014, 2016; Muñoz Arancibia et al. 2014; Béthermin et al. 2017), with the majority of them suggesting that ~ 70 per cent of the FIR-bright components should be physically unassociated. While some of these works find a higher median redshift in their simulations (Muñoz Arancibia et al. 2014; Cowley et al. 2014, 2016) than our data, these simulations were focused on an 850- μm selection, which should select higher redshifts, as seen in the observations (e.g. Casey et al. 2012). Both Hayward et al. (2013) and Béthermin et al. (2017) find similar typical redshifts. Cowley et al. (2014) suggest that the median difference in redshift between bright components is approximately $\Delta z = 1.0$. In particular, Béthermin et al. (2017) find that only 5 per cent of the blended FIR flux should come from additional components at consistent redshifts, similar to the results presented here.

Both the results from the theoretical works and the results presented here will influence other metrics used to understand the sub-mm/FIR population; e.g. the number counts¹³ and luminosity functions determined by observational works. Furthermore, Cowley et al. (2017) suggest that such blending of unrelated sources will inflate the clustering measurements by a factor of ~ 4 for a ~ 15 -arcsec beam, or more if the beam size is larger. Such clustering measurements (i.e. assessing the overabundance of sources along a line of sight where an FIR source is present), have previously been used to argue in favour of the merger origin hypothesis (Ivion et al. 2000, 2007). We note that in addition to the overestimation of the clustering predicted by Cowley et al. (2017), very large scale clustering could contribute to the signal seen, while still being at too large a scale to imply gravitational interactions (e.g. Fig. 5).

¹²It is unclear if the population traced by 24- μm flux is an unusual subset of FIR detections. We defer a comparison of the 3.6- μm FIR-bright counterparts and the 24- μm FIR-bright counterparts to a future work.

¹³A deeper analysis of the influence of how these results align with the extensive literature on number count predictions and observations is beyond the scope of this work.

The vast majority of existing observational works examining the multicomponent nature of bright FIR/sub-mm sources do not have redshift measurements (e.g. Hodge et al. 2013a; Karim et al. 2013; Koprowski et al. 2014; Simpson et al. 2015). These studies have instead used statistical arguments based on (e.g.) an excess of bright counterparts along the line of sight relative to what would be expected from a blank field (Simpson et al. 2015, see also Appendices A and B). This lack of redshift information means that there are only a few studies to which we can directly compare our results. The most similar work to that presented here is that of Simpson et al. (2017), who resolve 52 sources contributing to 30 bright SMGs, also selected to have 24- μm detections. In 11/30 sources, there are photometric redshifts presented for more than one component. Of those, six have contributing counterparts that are at inconsistent redshifts (considering the errors on each measurement). Another four have plausibly overlapping photo- z measurements (within errors), and one pair of components has identical measured redshifts. Without the full PDF, it is impossible to say how probable a consistent redshift measurement is for the redshifts that have overlapping error bars, as was done in this work. If we assume conservatively that all of them have >50 per cent likelihood of being found at a consistent redshift, we estimate that over half (54.5 per cent) of the Simpson et al. (2017) photo- z matched sample has incompatible redshift estimators. While this 50 per cent estimate is significantly lower than our current estimate, the selection criteria are very different in our work to the Simpson et al. (2017) work, and 54.5 per cent is a lower, conservative estimate to the incompatible redshift fraction. In both our work and in Simpson et al. (2017), it is fair to say that a majority of SMGs that are found to have multiple components contributing are comprised of physically unrelated galaxies.

In another recent work, Hayward et al. (2018) follow up interferometric ALMA observations of a small sample of 850- μm -selected sources that were found to have multiple FIR-bright components, finding redshifts for 9 of those 11. 6/9 sources (67 per cent) are determined to be at inconsistent redshifts, with large error on the percentages due to the small number statistics involved. The conclusions drawn here are entirely consistent with that of the Hayward et al. (2018) work, as they conclude that line-of-sight projections must be common in the data.

Similarly, Stach et al. (2018) use a combination of photometric redshifts with high-resolution ALMA imaging, very similar to our methodology. 44 per cent of their sample is found to have multiple bright components, and of those, Stach et al. (2018) report an excess of $\Delta z < 0.25$ counterparts, with 24/46 components found at this redshift, concluding that 30 per cent of the sample should be comprised of physical associations. While this is considerably higher than the fraction reported here, Stach et al. (2018) use much larger redshift tolerance in considering multiple counterparts to be at the same redshift, at $\Delta z = 0.25$ versus our widest bin of $\Delta z = 0.1$, which would naturally lead to a higher consistency fraction.

Wardlow et al. (2018) present the results of a CO(3–2) line search with ALMA for 6 single-dish detections, resolved into 14 bright counterparts. Consistent with what we present here, they find that 83 per cent of their FIR-bright samples are found to be at inconsistent redshifts with other FIR-bright counterparts. They conclude, as we do, that the FIR luminous objects are unlikely to be physically and gravitationally bound systems.

The other statistical work involving redshifts for a sub-mm sample is that of Chapman et al. (2005), which obtained 76 redshifts for a sample of sub-mm galaxies. However, these sources were selected from single-dish observations, so very few of them were already resolved into multiple flux-emitting components. Barger et al. (2012)

have only three sources that divide into multiple components; one of them has spectra for more than one of those components (Chapman et al. 2005; Barger, Cowie & Wang 2008), and they are found at inconsistent redshifts (including error bar uncertainties). Other works have similarly struggled with number statistics for their multicomponent systems; both Smolčić et al. (2012a) and Miettinen et al. (2015) have incompatible redshift fractions of 40 and 50 per cent, with samples of 5 and 6, respectively. Similarly, Danielson et al. (2017) report redshifts for a set of 52 SMGs taken from the ALESS sample, but of those, only three are found to have reliable redshifts for multiple components. Of those, they report no evidence for clustering along the line of sight, with redshift differences ranging from $\Delta z = 0.06$ –1.25. These results are entirely consistent with the picture that we present here, of strong contamination along the line of sight when multicomponent systems are present.

We note that the chain of thought that led to the broad assumption that many FIR/sub-mm sources are of a merger origin is an interesting one; we refer the interested reader to Appendices A and B, where we have undertaken a more detailed discussion of this point.

As mentioned earlier in this section, this study is limited in scope to only sources that are spatially resolved in the 3.6- μm data, i.e. typically separated by at least 2 arcsec.¹⁴ We are not sensitive to any merging populations that are in their final stages, or, as some studies have observed, multinucleus systems at sub-arcsecond resolutions (e.g. Ivison et al. 1998; Smail et al. 2003; Alaghband-Zadeh et al. 2012; Menéndez-Delmestre et al. 2013). Indeed, a recent study of a local Ultra-Luminous Infrared Galaxy (ULIRG¹⁵) triple system found that if it was to be found at high redshift, it would likely be misidentified as a clumpy galaxy or a small group (Väisänen et al. 2017). However, our results hold for any well resolved components at arcsecond scales, such as those found by Karim et al. (2013), where the typical separation is ~ 6 arcsec. At our typical redshift, 6 arcsec corresponds to a physical scale of ~ 49 kpc (Wright 2006), a scale at which galaxy–galaxy interactions are seen to impact the SFRs of galaxies in the local Universe (Scudder et al. 2012; Ellison et al. 2013; Patton et al. 2013). Furthermore, if one object in a pair is not FIR-bright, it would not be present in our sample, as we only consider sources that are FIR-bright. However, in local mergers, both galaxies in a major (i.e. roughly equal mass) merger are expected to be equally affected by the interaction and both should show significant star formation (e.g. Torrey et al. 2012).

We therefore propose that the FIR population in the COSMOS field, in particular the subset traced by 24- μm flux, is dominated by multiple flux-emitting components that are found at inconsistent redshifts. These galaxies are therefore not physically interacting, but are line-of-sight projections. Such projections are a well understood source of contamination in low-redshift galaxy pairs samples (e.g. Patton & Atfield 2008) and so it is perhaps unsurprising that given the large range of redshift visibility that the sub-mm bright population enjoys, that there is strong contamination along the line of sight. There remains a small fraction of these systems that are found at consistent redshifts both in the current work and in the literature (e.g. Tacconi et al. 2006). In this work, we do not intend to entirely rule out a merger origin for some fraction of the FIR-bright sources. We also recognize that some sources have been found to lie in protocluster environments (Hodge et al. 2013b; Ivison et al. 2013). However, considering that the vast majority of our *Herschel*

¹⁴At our typical redshift of $z=1$, this is a separation of 16.2 kpc (Wright 2006).

¹⁵ULIRGs are defined to have IR luminosity $L_{\text{IR}} > 10^{12} L_{\odot}$.

sources have spectro/photometric redshift PDFs that do not overlap at all, we must conclude that the majority of these galaxies are entirely gravitationally unrelated.

We therefore suggest that while the FIR population is more tightly clustered in redshift space than the overall distribution of photometric galaxies in the COSMOS field, this population is constructed of galaxies that are not physically associated, and the blending of their FIR light within the beam of *Herschel* has resulted in a boost to the detected FIR luminosity. We suggest that any merging population is either present at smaller spatial scales than we are sensitive to with 3.6- μm resolution, that SF has been triggered in these galaxies in a very asymmetric fashion, or that the SF in these galaxies is driven by non-merging processes. These processes would not need to produce SFRs as extreme as originally proposed, when all FIR flux had been assigned to a single physical system. Dividing the flux among two to three unrelated line-of-sight systems means that the SFR along the line of sight, while significant, is a considerable overestimation of the SFR in a physically bound system. The nature of the individual FIR-bright objects is impossible to constrain using the current data, and is likely to be a mixture of late-stage mergers, secular star formation, and other systems.

5 CONCLUSIONS

We briefly summarize the findings of our work here. We have investigated the physical association between a sample of FIR-bright (30 mJy \lesssim FIR flux \lesssim 110 mJy), blended sources in the COSMOS field. Our sample is selected to have both 3.6- and 24- μm counterparts, and in a previous work (Scudder et al. 2016) we used the XID+ software to assign best-fitting fluxes to each counterpart through Bayesian inference methods. In this work, we use only the sources identified as FIR-bright to investigate how close in redshift these contributing counterparts are.

(i) We select only those sources that were identified to be contributing more than 10 per cent of the total FIR source flux, and cross-match them with spectroscopic (Davies et al. 2014) and photometric (Laigle et al. 2016) redshift catalogues. We have a success rate in our cross-matching of 86 per cent, and the majority of the missing sources are near bright stars, which has contaminated their optical photometry.

(ii) We extract those FIR objects that have more than one bright component, and where more than one counterpart redshift has been identified. This results in a sample of 280 FIR objects, divided into 768 bright counterparts, with 736 pair permutations.

(iii) We find that the FIR-bright subsample is more densely clustered between $0.5 \leq z \leq 1.5$ than the photometric catalogue of Laigle et al. (2016). However, the FIR-bright sample appears to be consistent with a random sampling of this narrower redshift distribution, as KS tests on a scrambled version of the FIR-bright sample is unable to reject the null hypothesis of being drawn from the same parent population at $>3\sigma$.

(iv) We find that 72 per cent (536 pairs) of the FIR-bright sample has no overlap in their redshift distributions whatsoever, indicating 0 probability that they are found at a consistent ($\Delta z = 0.01$) redshift. Only 0.4 per cent of the sample (three individual pairs) is found to have more than 50 per cent likelihood of existing at consistent redshifts (where consistent is $\Delta z < 0.01$). Increasing the redshift tolerance does not substantially change these results.

In our sample, potentially interacting FIR counterparts comprise a minority of the overall population. These results caution that future studies of the sub-mm galaxy population require redshift

estimations to be made for all counterparts before any assumptions on physical associations can be made.

ACKNOWLEDGEMENTS

We thank the anonymous referee for a careful and thoughtful reading of this manuscript, and for their feedback that helped improve the presentation of this work.

JMS thanks Michael Zemcov, Andreas Papadopoulos, Steven Duivenvoorden, Gianfranco De Zotti, Mattia Vaccari, and Mathieu Béthermin for useful comments on a draft of this manuscript, which improved the clarity of this work.

JMS and SO acknowledge support from the Science and Technology Facilities Council (grant number ST/L000652/1).

JLW acknowledges the support of an STFC Ernest Rutherford Fellowship and has received additional support from a European Union COFUND/Durham Junior Research Fellowship under EU grant agreement number 609412, and STFC (ST/P004784/1)

This research made use of ASTROPY (<http://www.astropy.org>), a community-developed core PYTHON package for Astronomy (Collaboration et al. 2013), the MATPLOTLIB PYTHON plotting package (Hunter 2007), and NUMPY for array-like data manipulation (Van Der Walt, Colbert & Varoquaux 2011).

The research leading to these results has received funding from the Cooperation Programme (Space) of the European Union's Seventh Framework Programme FP7/2007-2013/ under REA grant agreement number [607254].

The *Herschel* spacecraft was designed, built, tested, and launched under a contract to the European Space Agency (ESA) managed by the *Herschel/Planck* Project team by an industrial consortium under the overall responsibility of the prime contractor Thales Alenia Space (Cannes), and including Astrium (Friedrichshafen) responsible for the payload module and for system testing at spacecraft level, Thales Alenia Space (Turin) responsible for the service module, and Astrium (Toulouse) responsible for the telescope, with in excess of a hundred subcontractors.

The Galaxy And Mass Assembly (GAMA) survey is a joint European-Australasian project based around a spectroscopic campaign using the Anglo-Australian Telescope. The GAMA input catalogue is based on data taken from the Sloan Digital Sky Survey and the United Kingdom Infrared Telescope (UKIRT) Infrared Deep Sky Survey. Complementary imaging of the GAMA regions is being obtained by a number of independent survey programmes including *Galaxy Evolution Explorer* (GALEX) Medium Imaging Survey, Very Large Telescope (VLT) Survey Telescope Kilo-Degree Survey (KiDS), Visible and Infrared Survey Telescope for Astronomy (VISTA) VISTA Kilo-Degree Infrared Galaxy Survey (VIKING), *Wide-field Infrared Survey Explorer* (WISE), *Herschel*-Astrophysical Terahertz Large Area Survey (H-ATLAS), Giant Metrewave Radio Telescope (GMRT), and Australian Square Kilometer Array Pathfinder (ASKAP) providing UV to radio coverage. GAMA is funded by the STFC (UK), the ARC (Australia), the AAO, and the participating institutions. The GAMA website is <http://www.gama-survey.org/>.

This work is based on data products from observations made with European Southern Observatory (ESO) Telescopes at the La Silla Paranal Observatory under ESO programme ID 179.A-2005 and on data products produced by TERAPIX and the Cambridge Astronomy Survey Unit on behalf of the UltraVISTA consortium. *Herschel* is an ESA space observatory with science instruments provided by European-led Principal Investigator consortia and with important participation from NASA.

REFERENCES

- Ahn C. P. et al., 2014, *ApJS*, 211, 17
- Alaghband-Zadeh S. et al., 2012, *MNRAS*, 424, 2232
- Amblard A. et al., 2011, *Nature*, 470, 510
- Aravena M., Younger J. D., Fazio G. G., Gurwell M., Espada D., Bertoldi F., Capak P., Wilner D., 2010, *ApJ*, 719, L15
- Barger A. J., Cowie L. L., Sanders D. B., Fulton E., Taniguchi Y., Sato Y., Kawara K., Okuda H., 1998, *Nature*, 394, 248
- Barger A. J., Cowie L. L., Wang W. H., 2008, *ApJ*, 689, 687
- Barger A. J., Wang W. H., Cowie L. L., Owen F. N., Chen C. C., Williams J. P., 2012, *ApJ*, 761, 89
- Baugh C. M., Lacey C. G., Frenk C. S., Granato G. L., Silva L., Bressan A., Benson A. J., Cole S., 2005, *MNRAS*, 356, 1191
- B  thermin M. et al., 2012, *A&A*, 542, A58
- B  thermin M. et al., 2017, *A&A*, 607, A89
- Blain A., 2002, *Phys. Rep.*, 369, 111
- Blain A. W., Chapman S. C., Smail I., Ivison R., 2004, *ApJ*, 611, 725
- Bothwell M. S. et al., 2010, *MNRAS*, 385, 893
- Bournaud F., Elmegreen B. G., 2009, *ApJ*, 694, L158
- Carilli C. L. et al., 2010, *ApJ*, 714, 1407
- Casey C. M. et al., 2012, *ApJ*, 761, 140
- Casey C. M., Narayanan D., Cooray A., 2014, *Phys. Rep.*, 541, 45
- Chapman S. C., Blain A. W., Smail I., Ivison R. J., 2005, *ApJ*, 622, 772
- Chen C.-C. et al., 2015, *ApJ*, 799, 194
- Cibinel A. et al., 2015, *ApJ*, 805, 181
- Clements D. L. et al., 2008, *MNRAS*, 387, 247
- Cole S., Lacey C. G., Baugh C. M., Frenk C. S., 2000, *MNRAS*, 319, 168
- Collaboration A. et al., 2013, *A&A*, 558, A33
- Cool R. J. et al., 2013, *ApJ*, 767, 118
- Cowley W. I., Lacey C. G., Baugh C. M., Cole S., 2014, *MNRAS*, 446, 1784
- Cowley W. I., Lacey C. G., Baugh C. M., Cole S., 2016, *MNRAS*, 461, 1621
- Cowley W. I., Lacey C. G., Baugh C. M., Cole S., Wilkinson A., 2017, *MNRAS*, 469, 3396
- Danielson A. L. R. et al., 2017, *ApJ*, 840, 78
- Dannerbauer H., Walter F., Morrison G., 2008, *ApJ*, 673, L127
- Dave R., Finlator K., Oppenheimer B. D., Fardal M., Katz N., Keres D., Weinberg D. H., 2010, *MNRAS*, 632, 736
- Davies L. J. M. et al., 2014, *MNRAS*, 447, 1014
- Dekel A. et al., 2009, *Nature*, 457, 451
- Dunlop J. S. et al., 2004, *MNRAS*, 350, 769
- Efstathiou A., Rowan-Robinson M., 2003, *MNRAS*, 343, 322
- Ellison S. L., Mendel J. T., Scudder J. M., Patton D. R., Palmer M. J. D., 2013, *MNRAS*, 430, 3128
- Engel H. et al., 2010, *ApJ*, 724, 233
- Farrah D. et al., 2006, *ApJ*, 641, L17
- Frayser D. T., Ivison R. J., Scoville N. Z., Yun M., Evans A. S., Smail I., Blain A. W., Kneib J. P., 1998, *ApJ*, 506, L7
- Frayser D. T. et al., 1999, *ApJ*, 514, L13
- Frayser D. T., Smail I., Ivison R. J., Scoville N. Z., 2000, *AJ*, 120, 1668
- Genel S. et al., 2008, *ApJ*, 688, 789
- Granato G. L., De Zotti G., Silva L., Bressan A., Danese L., 2004, *ApJ*, 688, 789
- Greve T. R. et al., 2005, *MNRAS*, 359, 1165
- Griffin M. J. et al., 2010, *A&A*, 518, L3
- Hainline L. J., Blain A. W., Greve T. R., Chapman S. C., Smail I., Ivison R. J., 2006, *ApJ*, 650, 614
- Hatsukade B. et al., 2010, *ApJ*, 711, 974
- Hayward C. C., Keres D., Jonsson P., Narayanan D., Cox T. J., Hernquist L., 2011, *ApJ*, 743, 159
- Hayward C. C., Narayanan D., Keres D., Jonsson P., Hopkins P. F., Cox T. J., Hernquist L., 2012, *MNRAS*, 428, 2529
- Hayward C. C., Behroozi P. S., Somerville R. S., Primack J. R., Moreno J., Wechsler R. H., 2013, *MNRAS*, 434, 2572
- Hayward C. C. et al., 2018, *MNRAS*, 476, 2278
- Hinshaw G. et al., 2013, *ApJS*, 208, 19
- Hodge J. A. et al., 2013a, *ApJ*, 768, 91
- Hodge J. A., Carilli C. L., Walter F., Daddi E., Riechers D., 2013b, *ApJ*, 776, 22
- Hopkins P. F. et al., 2009, *MNRAS*, 397, 802
- Hughes D. H. et al., 1998, *Nature*, 394, 241
- Hunter J. D., 2007, *Comput. Sci. Eng.*, 9, 90
- Hurley P. D. et al., 2017, *MNRAS*, 464, 885
- Immeli A., Samland M., Gerhard O., Westera P., 2003, *A&A*, 413, 547
- Iono D. et al., 2006, *ApJ*, 640, L1
- Ivison R. J., Smail I., Le Borgne J. F., Blain A. W., Kneib J. P., Bezecourt J., Kerr T. H., Davies J. K., 1998, *MNRAS*, 298, 583
- Ivison R. J., Dunlop J. S., Smail I., Dey A., Liu M. C., Graham J. R., 2000, *ApJ*, 542, 27
- Ivison R. J. et al., 2002, *MNRAS*, 337, 1
- Ivison R. J. et al., 2007, *MNRAS*, 380, 199
- Ivison R. J., Smail I., Papadopoulos P. P., Wold I., Richard J., Swinbank A. M., Kneib J. P., Owen F. N., 2010, *MNRAS*, 300, 369
- Ivison R. J. et al., 2013, *ApJ*, 772, 137
- Jonsson P., 2006, *MNRAS*, 372, 2
- Jonsson P., Groves B. A., Cox T. J., 2010, *MNRAS*, 403, 17
- Karim A. et al., 2013, *MNRAS*, 432, 2
- Koprowski M. P., Dunlop J. S., Michałowski M. J., Cirasuolo M., Bowler R. A. A., 2014, *MNRAS*, 444, 117
- Lacey C. G. et al., 2016, *MNRAS*, 462, 3854
- Laigle C. et al., 2016, *ApJS*, 224, 24
- Law D. R., Steidel C. C., Erb D. K., Pettini M., Reddy N. A., Shapley A. E., Adelberger K. L., Simenc D. J., 2007, *ApJ*, 656, 1
- Le Fevre O. et al., 2013, *A&A*, 554, A14
- Le Floc'h E. et al., 2009, *ApJ*, 703, 222
- Ledlow M. J., Smail I., Owen F. N., Keel W. C., Ivison R. J., Morrison G. E., 2002, *ApJ*, 577, L79
- Levenson L. et al., 2010, *MNRAS*, 409, 83
- Lilly S. J. et al., 2009, *ApJS*, 184, 218
- Marchesi S. et al., 2016, *ApJ*, 817, 34
- Men  ndez-Delmestre K., Blain A. W., Swinbank M., Smail I., Ivison R. J., Chapman S. C., Goncalves T. S., 2013, *ApJ*, 767, 151
- Miettinen O. et al., 2015, *A&A*, 577, A29
- Mu  oz Arancibia A. M., Navarrete F. P., Padilla N. D., Cora S. A., Gawiser E., Kurczynski P., Ruiz A. N., 2014, *MNRAS*, 446, 2291
- Narayanan D., Hayward C. C., Cox T. J., Hernquist L., Jonsson P., Younger J. D., Groves B., 2010, *MNRAS*, 401, 1613
- Narayanan D., et al., 2015, *Nature*, 525, 496
- Nayyeri H. et al., 2017, *ApJ*, 844, 82
- Neri R. et al., 2003, *ApJ*, 597, L113
- Nesvadba N. P. H. et al., 2007, *ApJ*, 657, 725
- Patton D. R., Atfield J. E., 2008, *ApJ*, 685, 235
- Patton D. R., Torrey P., Ellison S. L., Mendel J. T., Scudder J. M., 2013, *MNRAS*, 433, L59
- Pilbratt G. L. et al., 2010, *A&A*, 518, L1
- Richards E. A., 1999, *ApJ*, 513, L9
- Roseboom I. G. et al., 2010, *MNRAS*, 409, 48
- Rowan-Robinson M., Wang L., Farrah D., Rigopoulou D., Gruppioni C., Vaccari M., Marchetti L., Clements D. L., 2017, preprint (arXiv)
- Sanders D. B., Mirabel I. F., 1996, *ARA&A*, 34, 749
- Sanders D. B. et al., 2007, *ApJS*, 172, 86
- Scoville N. et al., 2007, *ApJS*, 172, 1
- Scudder J. M., Ellison S. L., Torrey P., Patton D. R., Mendel J. T., 2012, *MNRAS*, 426, 549
- Scudder J. M., Oliver S., Hurley P. D., Griffin M., Sargent M. T., Scott D., Wang L., Wardlow J. L., 2016, *MNRAS*, 460, 1119
- Silva L., Granato G. L., Bressan A., Danese L., 1998, *ApJ*, 509, 103
- Simpson J. M. et al., 2015, *ApJ*, 807, 128
- Simpson J. M. et al., 2017, *ApJ*, 839, 58
- Smail I., Ivison R. J., Blain A. W., 1997, *ApJ*, 490, L5
- Smail I., Ivison R. J., Owen F. N., Blain A. W., Kneib J. P., 2000, *ApJ*, 528, 612
- Smail I., Ivison R. J., Blain A. W., Kneib J. P., 2002, *MNRAS*, 331, 491
- Smail I., Chapman S. C., Ivison R. J., Blain A. W., Takata T., Heckman T. M., Dunlop J. S., Sekiguchi K., 2003, *MNRAS*, 342, 1185

- Smolčić V. et al., 2012a, *A&A*, 200, 10
 Smolčić V. et al., 2012b, *ApJS*, 548, A4
 Stach S. M. et al., 2018, *ApJ*, 860, 161
 Swinbank A. M. et al., 2008, *MNRAS*, 391, 420
 Swinbank A. M. et al., 2010, *MNRAS*, 588, 218
 Swinbank A. M. et al., 2011, *ApJ*, 742, 11
 Tacconi L. J. et al., 2006, *ApJ*, 640, 228
 Tacconi L. J. et al., 2008, *ApJ*, 680, 246
 Toomre A., 1964, *ApJ*, 139, 1217
 Torrey P., Cox T. J., Kewley L., Hernquist L., 2012, *ApJ*, 746, 108
 Trakhtenbrot B., Lira P., Netzer H., Ciccone C., Maiolino R., Shemmer O., 2017, *ApJ*, 836, 8
 Väisänen P., Reunanen J., Kotilainen J., Mattila S., Johansson P. H., Ramphul R., Romero-Cañizales C., Kuncarayakti H., 2017, *MNRAS*, 471, 2059
 Van Der Walt S., Colbert S. C., Varoquaux G., 2011, *Computing in Science and Engineering*, 13, 22
 Wang L. et al., 2014, *MNRAS*, 444, 2870
 Wardlow J. et al., 2018, *MNRAS*, 479, 3879
 Wiklind T. et al., 2014, *ApJ*, 785, 111
 Woods D. F., Geller M. J., 2007, *AJ*, 134, 527
 Wright E. L., 2006, *PASP*, 118, 1711
 Younger J. D. et al., 2007, *ApJ*, 671, 1531
 Younger J. D. et al., 2008, *ApJ*, 688, 59
 Younger J. D. et al., 2009, *ApJ*, 704, 803
 Younger J. D. et al., 2010, *MNRAS*, 407, 1268
 Zamojski M., Yan L., Dasyra K., Sajina A., Surace J., Heckman T., Helou G., 2011, *ApJ*, 730, 125

APPENDIX A: PREVIOUS OBSERVATIONAL RESULTS

The historical assumption that many sub-mm galaxies are interactions grew from a series of natural assumptions; first, that they drew obvious parallels with the ULIRG population at low redshift, in that they were similarly rare in their volumes, and both were very IR luminous. ULIRGs are almost entirely merging systems (Sanders & Mirabel 1996), so the interpretation of high- z IR-bright systems as the high- z extension of the ULIRG population was a straightforward one. However, testing this merger-induced star formation hypothesis observationally has proven to be a particular challenge, as it requires high-resolution data to both obtain accurate redshift estimations and accurately determine counterparts.

Obtaining any redshifts in the first place proved to be a considerable challenge, as sub-mm sources either had no multiwavelength counterpart (Frayer et al. 2000; Dannerbauer, Walter & Morrison 2008) or had a number of potentially contributing counterparts (Hughes et al. 1998; Hatsukade et al. 2010), and in either case, photometric redshifts were particularly badly constrained. Of the five SMG sources, Hughes et al. (1998) found somewhere between two and seven feasible counterparts, each with their own, generally poorly constrained, redshift estimates. Other work from this era struggled with the same problems of small number statistics and an overabundance of possible counterparts (e.g. Richards 1999).

Where redshifts could be obtained, a small number of these galaxies were observed in high resolution with (e.g.) the Plateau de Bure interferometer or the Very Large Array. These samples typically presented new observations of only one to three systems (Ledlow et al. 2002; Neri et al. 2003; Greve et al. 2005; Hainline et al. 2006; Tacconi et al. 2006, 2008; Aravena et al. 2010; Bothwell et al. 2010; Engel et al. 2010; Ivison et al. 2010) and found that these systems were very irregular in their morphologies, showing either clumpy components, irregular line profiles, or extremely high gas densities. Greve et al. (2005) note that with the sorts of gas densities being observed in these systems, the galaxies should fail the Toomre gas stability Q parameter (Toomre 1964), and be extremely prone

to collapse, either through disc fragmentation, or through merger-induced instabilities. Many of these works interpret the disorder in the line profiles or the gas density measurements as the signatures of merging events (Tacconi et al. 2006, 2008; Engel et al. 2010). It is not particularly clear whether the high gas surface densities should be due to interaction-driven tidal torquing, as this torque has been shown to be relatively ineffective in very gas-rich systems (Hopkins et al. 2009). The torquing mechanism requires the presence of a considerable stellar bar, or the gas inflow to the centre of the system becomes extremely inefficient.

Individual clumps have also been taken as signs of interactions, or pre-coalescence mergers (Smail et al. 2003; Nesvadba et al. 2007). Generally, asymmetric or ‘messy’ morphologies are attributed to the influence of interactions between galaxies (Engel et al. 2010; Younger et al. 2010; Menéndez-Delmestre et al. 2013; Chen et al. 2015). At low redshift, such asymmetries are good tracers of gravitational interactions between galaxies. The clumpy nature of high-redshift galaxies on small scales has also become considerably more difficult to interpret; studies like that of Law et al. (2007) and Cibinel et al. (2015) show that morphological irregularities do not seem to correlate with any other properties of the galaxy, and so these asymmetric morphologies or multiple components in high-redshift systems are either not good proxies of an interacting system, or the interaction is not changing the observational properties of the galaxy. Law et al. (2007) specifically find that the sub-mm population of Chapman et al. (2005) is no more likely than an isolated sample to show multiple strong nuclei. Similar results were found in Swinbank et al. (2010), with no excess of asymmetry found in the SMG sample. Some works are beginning to conclude that some intermediate redshift galaxies are very messy discs fuelled by pristine gas infall (e.g. Carilli et al. 2010), which explains the ordered nature of their rotation. Nayyeri et al. (2017) find that for a single-lensed galaxy, the SFR is consistent with the typical SFR for galaxies of that stellar mass at a redshift of 2.6.

Studies that were more statistical in nature found that the overabundance of possible counterparts persisted beyond the brightest sources. Such studies either relied on radio source counterparts to identify a *single* ‘true’ counterpart IDs (e.g. Ivison et al. 2007), or found the optical counterpart that aligned most closely with the centroid of the sub-mm detection. (The exception to this was if the closest galaxy appeared to be a giant elliptical without much star formation, whereupon gravitational lensing would be suspected of a fainter, bluer object.) These studies still often found multiple possible counterparts to the FIR flux, and the interpretation of this statistical overabundance was explained using a probabilistic argument. These sub-mm counterparts had more possible counterparts along the line of sight than could be expected by randomly sampling the field; this led many works to the conclusion that these counterparts must be physically associated (Ivison et al. 2000, 2007). Hodge et al. (2013a) further noted that while they find an excess of sources in the majority of these fields with ALMA observations, there is no excess of sources at the smallest separations, which is suggested to be due to a merger origin.

However, the true counterparts must always be identified in the sub-mm in order to be conclusive, and prior to ALMA, this meant that many works were conducted with the SMA. However, due to the longer observing times required, this usually resulted in samples that were rather small (Iono et al. 2006; Younger et al. 2007, 2008, 2009, 2010; Hatsukade et al. 2010) sensitive to the brightest counterparts, and primarily used for the testing of the reliability of multiwavelength counterpart identification.

Our understanding of multiplicity took another turn with the advent of high-resolution ALMA follow-up of single-dish data, where it was discovered that a considerable fraction of the sub-mm detected objects were resolved into multiple flux-emitting components (e.g. Hodge et al. 2013a; Karim et al. 2013; Simpson et al. 2015, though cf. Koprowski et al. 2014). These surveys, however, had no intrinsic redshift measurements associated with any of the individual flux-emitting components, as they are continuum studies, and the sub-mm population is well known to be luminous over a wide range of redshifts. However, the statistical argument of the overabundance of components along the line of sight to a sub-mm source implying a physical association (i.e. interactions) persisted (Simpson et al. 2015).

Without measurements of the spectroscopic or photometric redshifts, this assessment of the overabundance of flux-emitting components as physically associated is impossible to ascertain directly. Existing studies of the redshift distributions of the resolved sub-mm galaxy population are still relatively limited in statistical power (e.g. Hatsukade et al. 2010; Barger et al. 2012; Smolčić et al. 2012b), or contain a number of poorly constrained photometric redshifts, where the range in possible redshifts is sufficiently broad that it is impossible to rule out a consistent solution (e.g. Younger et al. 2009), though we note that the best-fitting solutions for the galaxies in Younger et al. (2009) are widely separated in redshift space. Smolčić et al. (2012a) presented interferometric imaging of a sample of 19 LABOCA-selected galaxies, where several of the galaxies had photometric redshift information. Of the five with multiple components and multiple redshifts, two must be at inconsistent redshifts; the remaining three are potentially consistent within the very wide error bars presented. Miettinen et al. (2015) also presented redshift information for a subset of the multiple component systems; of the six systems with more than one redshift associated, three of them have inconsistent redshifts, and the other three are presented only as lower limits to the redshift estimate, so it is impossible to determine whether the remainder is also inconsistent.

APPENDIX B: THEORETICAL RESULTS

Simulations of the high-redshift galaxy population have historically struggled to reproduce the extreme infrared luminosities required to explain the sub-mm galaxy population, and have invoked a number of possible explanations in order to explain the nature of these sub-mm luminous sources, which have largely been interpreted as single galaxies.

With the observational base seemingly convinced that the sub-mm galaxy population was largely constructed of interactions, it should come as no surprise that many of the simulations set about testing this assessment. The most luminous galaxies have often been ascribed to merger-induced starbursts (Genel et al. 2008; Dekel et al. 2009; Narayanan et al. 2010; Hayward et al. 2011) either through an abundance matching method (e.g. Genel et al. 2008; Dekel et al. 2009), by directly modelling the sub-mm flux through radiative

transfer codes such as SUNRISE (Jonsson 2006; Jonsson, Groves & Cox 2010; Narayanan et al. 2010; Hayward et al. 2011); with codes like GRASIL (Silva et al. 1998; Swinbank et al. 2008), the geometry of the system could also be taken into account. However, even amongst these works, the slightly less FIR luminous (though still certainly detectable) populations rapidly became heterogeneous, with a number of works suggesting that the less luminous population was a mixture of interacting and non-interacting systems (Dave et al. 2010; Narayanan et al. 2010; Hayward et al. 2011). Others suggested that these less luminous systems were being fuelled by pristine gas infalling all the way to the centre of the galaxy’s halo (Granato et al. 2004; Genel et al. 2008; Dekel et al. 2009; Narayanan et al. 2015).

Other simulations, however, suggested that mergers should not play a major role in triggering the star formation within these luminous sub-mm galaxies. Instead, these gas-rich systems are hypothesized to be simply too unstable to survive without large-scale disc fragmentation (Immeli et al. 2003; Bournaud & Elmegreen 2009; Lacey et al. 2016), which would then transform a gas-rich disc galaxy into something highly morphologically disturbed, without requiring any kind of external perturbation, like an interaction. These simulations expect to observations to reveal significant clumps of star formation within the disc, and predict that these clumps are the results of vigorous star formation in systems that are gas-dominated (Bournaud & Elmegreen 2009) and without a strong bulge component (Immeli et al. 2003).

The last suggestion used to explain the extreme SFRs in sub-mm sources has been an alteration of the IMF. A variable IMF is invoked as a way to inflate the IR luminosity without needing to dramatically increase the SFR in high-redshift systems. If there were a mode of star formation (perhaps triggered by minor interactions) that preferentially formed high-mass stars, then the UV luminosity would be increased on average. These high-mass stars are also producers of significant volumes of dust, which then provides the mechanism to boost the IR luminosity observed. The dust produced by these stars will be heated by the UV radiation of other massive stars, creating an excess of IR light. The most extreme of these variations to the IMF was proposed by Baugh et al. (2005) in an early version of the GALFORM model (Cole et al. 2000). Some elements of this IMF variability have persisted in subsequent versions of GALFORM (Lacey et al. 2016), though the change in the IMF between normal and starburst modes is not quite as extreme.

It has only been recently that the simulations have begun to tackle observational biases in the FIR samples more thoroughly; since these studies into the biases of single-dish observations, a consensus has emerged that FIR-bright sources in single-dish data are likely to be strongly blended, and that those blends are unlikely to be physical associations of galaxies (Hayward et al. 2013; Cowley et al. 2014, 2016; Muñoz Arancibia et al. 2014; Béthermin et al. 2017).

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.