

The SAMI Galaxy Survey: understanding observations of large-scale outflows at low redshift with EAGLE simulations

E. Tescari,^{1,2*} L. Cortese,³ C. Power,^{2,3} J. S. B. Wyithe,^{1,2} I.-T. Ho,^{4,5,6} R. A. Crain,⁷ J. Bland-Hawthorn,^{2,8} S. M. Croom,^{2,8} L. J. Kewley,⁵ J. Schaye,⁹ R. G. Bower,¹⁰ T. Theuns,¹⁰ M. Schaller,¹⁰ L. Barnes,⁸ S. Brough,^{2,11} J. J. Bryant,^{2,8,11} M. Goodwin,¹¹ M. L. P. Gunawardhana,¹⁰ J. S. Lawrence,¹¹ S. K. Leslie,^{2,5,6} Á. R. López-Sánchez,^{11,12} N. P. F. Lorente,¹¹ A. M. Medling,^{5,13†} S. N. Richards,^{2,8,11} S. M. Sweet⁵ and C. Tonini¹

¹*School of Physics, the University of Melbourne, Parkville, VIC 3010, Australia*

²*ARC Centre of Excellence for All-Sky Astrophysics (CAASTRO)*

³*International Centre for Radio Astronomy Research (ICRAR), the University of Western Australia, 35 Stirling Highway, Crawley, WA 6009, Australia*

⁴*Institute for Astronomy, University of Hawaii, 2680 Woodlawn Drive, Honolulu, HI 96822, USA*

⁵*Research School of Astronomy and Astrophysics, Australian National University, Cotter Road, Weston Creek, ACT 2611, Australia*

⁶*Max Planck Institute for Astronomy, Königstuhl 17, D-69117 Heidelberg, Germany*

⁷*Astrophysics Research Institute, Liverpool John Moores University, 146 Brownlow Hill, Liverpool L3 5RF, UK*

⁸*Sydney Institute for Astronomy, School of Physics, University of Sydney, Sydney, NSW 2006, Australia*

⁹*Leiden Observatory, Leiden University, PO Box 9513, NL-2300 RA Leiden, the Netherlands*

¹⁰*Institute for Computational Cosmology, Department of Physics, Durham University, South Road, Durham DH1 3LE, UK*

¹¹*Australian Astronomical Observatory, PO Box 915, North Ryde, NSW 1670, Australia*

¹²*Department of Physics and Astronomy, Macquarie University, Sydney, NSW 2109, Australia*

¹³*Cahill Center for Astronomy and Astrophysics, California Institute of Technology, MS 249-17 Pasadena, CA 91125, USA*

Accepted 2017 September 5. Received 2017 September 4; in original form 2016 December 5

ABSTRACT

This work presents a study of galactic outflows driven by stellar feedback. We extract main-sequence disc galaxies with stellar mass $10^9 \leq M_*/M_\odot \leq 5.7 \times 10^{10}$ at redshift $z = 0$ from the highest resolution cosmological simulation of the Evolution and Assembly of GaLaxies and their Environments (EAGLE) set. Synthetic gas rotation velocity and velocity dispersion (σ) maps are created and compared to observations of disc galaxies obtained with the Sydney-AAO (Australian Astronomical Observatory) Multi-object Integral field spectrograph (SAMI), where σ -values greater than 150 km s^{-1} are most naturally explained by bipolar outflows powered by starburst activity. We find that the extension of the simulated edge-on (pixelated) velocity dispersion probability distribution depends on stellar mass and star formation rate surface density (Σ_{SFR}), with low- $M_*/$ low- Σ_{SFR} galaxies showing a narrow peak at low σ ($\sim 30 \text{ km s}^{-1}$) and more active, high- $M_*/$ high- Σ_{SFR} galaxies reaching $\sigma > 150 \text{ km s}^{-1}$. Although supernova-driven galactic winds in the EAGLE simulations may not entrain enough gas with $T < 10^5 \text{ K}$ compared to observed galaxies, we find that gas temperature is a good proxy for the presence of outflows. There is a direct correlation between the thermal state of the gas and its state of motion as described by the σ -distribution. The following equivalence relations hold in EAGLE: (i) low- σ peak \Leftrightarrow disc of the galaxy \Leftrightarrow gas with $T < 10^5 \text{ K}$; (ii) high- σ tail \Leftrightarrow galactic winds \Leftrightarrow gas with $T \geq 10^5 \text{ K}$.

Key words: methods: numerical – galaxies: evolution – galaxies: kinematics and dynamics.

* E-mail: etescari@unimelb.edu.au

† Hubble Fellow.

1 INTRODUCTION

In the last few years, low-redshift galaxy surveys have been transformed by the advent of integral field spectroscopy (IFS). IFS enables astronomers to obtain spatially resolved spectroscopic information across different regions of the same object. This technological progress has considerably improved our understanding of various galactic properties (previously estimated using only a single aperture measurement per target) and changed the way we study and classify galaxies (see the review by Cappellari 2016).

A number of IFS surveys have already been carried out and others are currently ongoing, e.g. DiskMass (Bershady et al. 2010), ATLAS^{3D} (Cappellari et al. 2011), CALIFA (Sánchez et al. 2012) and MaNGA (Bundy et al. 2015). In this work, we utilize the results of the SAMI Galaxy Survey (Bryant et al. 2015). SAMI is the Sydney-AAO (Australian Astronomical Observatory) Multi-object Integral field spectrograph, mounted at the prime focus of the Anglo-Australian Telescope (AAT) and attached to the AAOmega spectrograph (Sharp et al. 2006). It allows for the simultaneous observations of 12 objects and one calibration star by means of fibre *hexabundles* (Bland-Hawthorn et al. 2011; Bryant et al. 2014), each composed of 61 optical fibres fused together for a field of view of 15 arcsec (Croom et al. 2012). The aim of the survey is to observe ~ 3400 galaxies in a wide range of stellar masses and environments within the redshift interval $0.004 < z < 0.095$. The interested reader can find a discussion of the SAMI data reduction in Sharp et al. (2015), the early data release in Allen et al. (2015) and the data release one details in Green et al. (2017). One of the key scientific drivers is the study of feedback processes related to star formation activity.

Galactic winds affect galaxies and their surrounding environments by regulating the star formation rate (SFR) and therefore shaping the luminosity function, and by enriching the intergalactic medium (see the reviews by Veilleux, Cecil & Bland-Hawthorn 2005; Bland-Hawthorn, Veilleux & Cecil 2007). Bipolar stellar/supernova (SN)-driven outflows appear to be ubiquitous at high redshift (Shapley 2011), while at low z they are readily detected only in starburst galaxies (Heckman et al. 2015). Considerable observational effort has been spent to constrain the thermodynamic and kinematic properties of galactic winds (e.g. Steidel et al. 2010; Nestor et al. 2011; Martin et al. 2012; Leitherer et al. 2013; Rubin et al. 2014; Kacprzak et al. 2015; Zhu et al. 2015; Chisholm et al. 2016a,b; Cicone, Maiolino & Marconi 2016; Pereira-Santaella et al. 2016; Leslie et al. 2017). Despite the plethora of data available, a completely consistent picture of stellar feedback remains elusive.¹ For example, the interplay between different energy and momentum injection mechanisms (e.g. radiation pressure – Murray, Ménard & Thompson 2011, thermal runaway – Li et al. 2015, cosmic rays – Salem & Bryan 2014; Wiener, Pfrommer & Oh 2017) is still poorly understood. Moreover, observations of cold and neutral gas clouds entrained in hot, ionized outflows (e.g. Sarzi et al. 2016) are difficult to address theoretically (Scannapieco & Brügger 2015; Brügger & Scannapieco 2016; Thompson et al. 2016; Zhang et al. 2017).

Analytical and numerical models are essential to explore the physics of galactic winds and to interpret observed data (see the recent works of Barai et al. 2013, 2015; Keller, Wadsley & Couchman 2015; Muratov et al. 2015; Rosdahl et al. 2015;

Bustard, Zweibel & D’Onghia 2016; Ceverino et al. 2016; Christensen et al. 2016; Girichidis et al. 2016; Martizzi et al. 2016; Meiksin 2016; Tanner, Cecil & Heitsch 2016, 2017; Anglés-Alcázar et al. 2017; Hayward & Hopkins 2017; Kim, Ostriker & Raileanu 2017; Li, Bryan & Ostriker 2017; Ruzszkowski, Yang & Zweibel 2017; Schneider & Robertson 2017; Zhang & Davis 2017). Properly describing the variety of scales (from star forming molecular clouds to the intergalactic medium) and complexity of processes involved is a challenging task, especially in cosmological simulations aimed at reproducing representative volumes of the Universe. For this reason, phenomenological sub-resolution prescriptions are usually adopted in simulations of galaxy formation and evolution. Major progress has been made in this field during the last 5 yr (cf. the reviews by Dale 2015; Somerville & Davé 2015, and references therein). In the future, increasingly detailed observations will call for more sophisticated codes that include additional physics implemented using advanced numerical techniques. In particular, IFS data promise to play a critical role in the investigation of galactic winds (Sharp & Bland-Hawthorn 2010).

The potential of SAMI for this fundamental scientific research was confirmed in the first commissioning run, when Fogarty et al. (2012) serendipitously discovered a spiral galaxy (ESO 185-G031 at $z = 0.016$) showing diffuse emission along the minor axis consistent with starburst-driven galactic winds. Later, Ho et al. (2014) investigated an isolated disc galaxy (SDSS J090005.05+000446.7 at $z = 0.05386$) that exhibits emission line profiles differently skewed in different regions. Accurate modelling revealed the presence of major outflows affecting the velocity dispersion (σ) distribution of gas by introducing shock excitation on the top of stellar photoionization.² Based on this pilot study, Ho et al. (2016b) developed an empirical method to identify wind-dominated galaxies and applied this to a sample of 40 edge-on main-sequence SAMI galaxies. The method quantifies the asymmetry of the extraplanar gas and the relative importance of its velocity dispersion over the maximum rotation velocity of the disc.

In this work, we repeat the analyses of Ho et al. (2014) and Ho et al. (2016b) on synthetic disc galaxies extracted from state-of-the-art cosmological smoothed particle hydrodynamic (SPH) simulations. Note that we use the terms *galactic winds* and *outflows* as synonyms to identify gas that is moving away from the plane of our galaxies. This includes both material that is in the process of leaving the galaxy and gas that will eventually stop and fall back (i.e. galactic fountains). We adopt a different approach with respect to other theoretical investigations designed to mimic the observations of current IFS surveys and based on hydrodynamic simulations. In particular, Naab et al. (2014) for ATLAS^{3D} and Guidi et al. (2016a) for CALIFA use ‘zoom-in’ simulations of individual galaxies, while our synthetic sample is extracted from a large cosmological box. Guidi et al. (2016a) also include radiative transfer processes, while we estimate the kinematic state of the gas directly from the SPH scheme. Differently from these two works, the main goal of our analysis is reproducing the kinematic features seen in the outflows of SAMI disc galaxies, rather than the exact set-up of the observations.

The paper is organized as follows. In Section 2, we present the simulations used for this work, our sample of synthetic galaxies and the methodology adopted. In Sections 3 and 4, we study the impact of various galactic properties on the velocity dispersion

¹ The same is true for feedback associated with active galactic nuclei (AGNs), which is not considered in this work.

² When we refer to observations, *velocity dispersion* is equivalent to *line broadening*.

distribution, and compare with SAMI observations of galaxies with outflows. In Section 5, we apply the empirical identification of wind-dominated SAMI galaxies of Ho et al. (2016b) to our simulated sample. We discuss our results and conclude in Section 6. Finally, in Appendices A and B we present resolution tests and verify our analysis using idealized simulations of disc galaxies.

2 EAGLE SIMULATIONS

The simulations used in this work are part of the Virgo Consortium’s Evolution and Assembly of GaLaxies and their Environments (EAGLE) project (Crain et al. 2015; Schaye et al. 2015). The EAGLE set includes hydrodynamic high-resolution/large-box-size cosmological simulations, run with a modified version of the SPH code GADGET-3 (Springel 2005). The adopted cosmology is a standard Λ CDM model calibrated according to Planck Collaboration et al. (2014) data ($\Omega_{\Lambda} = 0.693$, $\Omega_{\text{m}} = 0.307$, $\Omega_{\text{b}} = 0.04825$, $h = 0.6777$, $\sigma_8 = 0.8288$ and $n_s = 0.9611$). Parallel friends-of-friends and SUBFIND algorithms (Springel et al. 2001; Dolag et al. 2009) identify collapsed dark matter haloes and populate them with galaxies/substructures.

2.1 Star formation and feedback

Amongst the technical improvements implemented in EAGLE (e.g. the new ANARCHY formulation of SPH described in Schaller et al. 2015), the subgrid model for feedback associated with star formation is particularly important for this study. Each star particle represents a simple stellar population of stars with mass in the range $0.1\text{--}100 M_{\odot}$, distributed according to a Chabrier (2003) initial mass function (IMF). Metallicity-dependent lifetimes are used to identify which stars reach the end of the main-sequence phase as the simulation evolves. Then, the fraction of mass lost through core collapse & type Ia SNe and winds from asymptotic giant branch & massive stars is calculated for each element that is important for radiative cooling (Wiersma, Schaye & Smith 2009a; Wiersma et al. 2009b).

SNe and stellar winds deposit energy, momentum and radiation into the interstellar medium (ISM). When the SFR is high enough, the associated feedback can expel considerable quantities of gas from the ISM generating large-scale galactic winds. In EAGLE, stellar feedback is implemented thermally without shutting off radiative cooling or decoupling particles from the hydrodynamic scheme.³ As a result, galactic outflows develop via pressure gradients established by the heating, without the need to specify wind velocities, directions or mass loading factors. To avoid a rapid dissipation of the injected SN energy due to efficient cooling, the temperature increment of heated resolution elements is imposed to be $\Delta T_{\text{SF}} = 10^{7.5}$ K (Dalla Vecchia & Schaye 2012). The efficiency of feedback scales negatively with metallicity and positively with gas density⁴ and was calibrated to reproduce the observed galaxy stellar mass function (GSMF) and mass-size relation of disc galaxies at $z = 0.1$ (Trayford et al. 2015; Furlong et al. 2017). The interested reader can find an extensive discussion of the subgrid physics in Schaye et al. (2015) and of the feedback calibration in Crain et al. (2015).

³ AGN feedback is also implemented thermally, but its role is negligible for the analysis presented in this paper.

⁴ Physical thermal losses increase with metallicity, while the density scaling accounts for spurious, resolution dependent radiative losses (Crain et al. 2015; Schaye et al. 2015).

In this work, we use a single simulation snapshot at $z = 0$. When considering a static distribution of particles and their properties, EAGLE’s feedback scheme makes it harder to identify and track wind particles outflowing from galaxies,⁵ with respect to simulations based on GADGET-3 where stellar feedback is implemented kinetically (rather than thermally) and wind particles are (a) allowed to leave the galaxy by temporarily disabling the hydrodynamic interactions (Springel & Hernquist 2003) and (b) tagged during the time they spend decoupled from the hydrodynamics (see e.g. the ANGUS project; Tescari et al. 2014). As mentioned above, EAGLE simulations develop mass loading by heating relatively few ISM particles and allowing winds to form via pressure gradients, rather than directly ejecting a number of particles specified by the subgrid scheme. This leads to entrainment: most outflowing gas was never heated directly by the subgrid scheme, but was heated by shocks/compression resulting from the initial energy injection (Bahé et al. 2016). At the relatively low masses considered in this work ($M_{*} \leq 5.7 \times 10^{10} M_{\odot}$, see below), young stars and SNe in EAGLE drive high-entropy winds that are more buoyant than any tenuous galaxy’s corona: the majority of gas leaves in a hot ($T > 10^5$ K), diffuse form rather than through ballistic winds (Bower et al. 2017). There are pros and cons. Advantages: gas temperature is a good first-order proxy for the presence or absence of galactic winds (Section 4.2). Disadvantages: as noted by Turner et al. (2016), outflows driven by stellar feedback may not entrain enough gas with $T < 10^5$ K (Sections 3.1 and 3.2).

Note that, following Schaye & Dalla Vecchia (2008), in EAGLE the SFR depends on pressure (rather than density) through an equation of state $P = P_{\text{eos}}(\rho_{\text{gas}})$. Since the simulations do not have enough resolution to model the interstellar, cold gas where star formation occurs, a temperature floor (normalized to $T_{\text{eos}} = 8000$ K at $n_{\text{H}} = 0.1 \text{ cm}^{-3}$, which is typical of the warm ISM) is imposed. We stress that the temperature of star-forming gas in EAGLE cannot be interpreted as a measure of the gas kinetic energy, but simply reflects the effective pressure imposed on the unresolved, multi-phase ISM (Schaye & Dalla Vecchia 2008; Schaye et al. 2015). SFR in galaxies correlates with the emission of H α radiation at $T \sim 10^4$ K (Kennicutt 1998). In our post-process analysis, we assume that any gas particle with SFR > 0 has $T = 10^4$ K and use EAGLE star-forming gas as a proxy for gas that would be detected in H α (see also Section 2.4).

2.2 Recal-L025N0752

High spatial/mass resolution is crucial to robustly sample both the gas distribution in galaxies and, especially, the relatively small fraction of gas outflowing from them. Hence, for this work we used the highest resolution configuration available in the EAGLE set: L025N0752. As the name suggests, a cubic volume of linear size $L = 25$ comoving Mpc (cMpc) is sampled with $N = 2 \times 752^3$ dark matter (DM) + gas particles with initial mass $1.21 \times 10^6 M_{\odot}$ and $2.26 \times 10^5 M_{\odot}$, respectively. The comoving Plummer-equivalent gravitational softening length is 1.33 ckpc and the maximum proper softening length is 0.35 kpc.

This configuration comes in two different set-ups: *Ref-L025N0752* and *Recal-L025N0752*. The first one is the initial reference set-up, while in the second the subgrid stellar and AGN

⁵ In principle, using a series of high time resolution snapshots would allow one to catch thermodynamic changes as they happen (Crain et al. in preparation).




Figure 1. Top row: Positions in physical kpc of gas (black dots) and star (orange dots) particles for the galaxy of the simulated sample with the highest SFR. This object has total (i.e. as determined by `SUBFIND`) $M_* = 4.30 \times 10^{10} M_\odot$, $M_{\text{gas}} = 1.94 \times 10^{11} M_\odot$, $M_{\text{tot}} = 1.89 \times 10^{12} M_\odot$, $\text{SFR} = 6.77 M_\odot \text{yr}^{-1}$ and $\log(\text{sSFR}/\text{yr}^{-1}) = -9.80$. The stellar and gas mass inside the $(30 \text{ kpc})^3$ cube are, respectively, $M_{*,c} = 3.51 \times 10^{10} M_\odot$ and $M_{\text{gas},c} = 1.19 \times 10^{10} M_\odot$. Left-hand panel: xz edge-on projection. Middle panel: xy face-on projection. Right-hand panel: yz edge-on projection. Bottom left-hand panel: $\text{SFR}-M_*$ relation for our simulated galaxies. The grey solid (+ triple dot-dashed) line is the best-fitting $\text{SFR}-M_*$ relation for star-forming local galaxies of Renzini & Peng (2015). The synthetic sample represents disc galaxies on the main sequence. Bottom right-hand panel: simulated specific $\text{SFR}-M_*$ relation. The vertical and horizontal dashed lines mark, respectively, the median M_* and sSFR of the final sample: $\log(M_*/M_\odot) = 9.78$, $\log(\text{sSFR}/\text{yr}^{-1}) = -10.04$. To facilitate the subsequent analysis, we divided the plot in four quadrants: Q1 = low M_* – low sSFR, Q2 = low M_* – high sSFR, Q3 = high M_* – low sSFR and Q4 = high M_* – high sSFR (see the text).

feedback parameter values were re-calibrated to better match the observed low-redshift GSMF (Schaye et al. 2015). In practice, the main difference is that feedback is slightly more effective in *Recal*. This prevents overcooling problems and leads to more realistic gas and stellar distributions in galaxies. For this reason, we used *Recal-L025N0752* for the analysis presented in this paper.

2.3 Galaxy sample

For this project, we have developed a pipeline to optimize the analysis of EAGLE simulations. The pipeline first (and only once) loads the original EAGLE snapshot and reads the output of `SUBFIND` (i.e. the catalogue of substructures within DM haloes). Then it extracts and saves only the information needed by the user (e.g. only galaxies with stellar mass, M_* , and/or specific SFR, $\text{sSFR} \equiv \text{SFR}/M_*$, in a given range). Since the original snapshot can be several gigabytes in size, this procedure drastically reduces both memory and time access requirements, speeding up considerably the subsequent analysis.

We used the pipeline to extract cubes of size 30 physical kpc around all the galaxies with $M_* \geq 10^9 M_\odot$ from *Recal-L025N0752* at $z = 0$ (taking into account periodic boundary conditions and a buffer of extra 70 kpc per side for SPH interpolation, see Section 2.4). Each cube is a `GADGET` format file containing a new header and the following information for gas (g) and star (s) particles: position ($g+s$), velocity ($g+s$), mass ($g+s$), temperature (g), density (g), smoothing length (g), SFR (g), metallicity ($g+s$) and age (s). The initial sample included 266 galaxies.

We then rotated the particle distribution ($g+s$) around the gravitational potential minimum (using the angular momentum per unit mass of star particles) in order to place each galaxy face-on in the xy plane and edge-on in the xz and yz planes. Accordingly, we rotated the velocity vector of each particle in the cube and used the velocity of the (rotated) stellar centre of mass as the velocity reference frame. At this point, we visually inspected the sample and only selected unperturbed galaxies with a prominent disc structure in both gas and stars, a number of gas particles (N_{gas}) inside the $30+70$ kpc cube sufficient to make our analysis robust, and fairly regular/symmetric gas rotation velocity maps (constructed as

explained in Section 2.4). The final sample includes 43 galaxies with $9.02 \leq \log(M_*/M_\odot) \leq 10.76$ and $7.8 \times 10^3 \lesssim N_{\text{gas}} \lesssim 9.4 \times 10^4$ ($N_{\text{gas}} \approx 3.8 \times 10^4$).⁶ In the top row of Fig. 1, we plot positions of gas (black dots) and star (orange dots) particles for the galaxy with the highest SFR. The left-hand and right-hand panels show the edge-on xz and yz projections: the galactic disc is clearly visible in both star and gas components. The middle panel shows the face-on xy projection. The gas distribution is arranged in a complex clumpy structure as a result of the interplay between star formation and associated feedback processes.

The bottom left-hand panel of Fig. 1 shows the distribution in the SFR– M_* plane of our final sample of 43 galaxies. The minimum and maximum SFRs are 0.065 and 6.77 $M_\odot \text{ yr}^{-1}$. The grey solid (+ triple dot-dashed) line is the best-fitting SFR– M_* relation for star-forming local galaxies of Renzini & Peng (2015): $\log(\text{SFR}/[M_\odot \text{ yr}^{-1}]) = (0.76 \pm 0.01)\log(M_*/M_\odot) - 7.64 \pm 0.02$. The final sample represents disc galaxies on the main sequence. We plot the simulated specific SFR– M_* relation in the bottom right-hand panel of Fig. 1. The vertical and horizontal dashed lines mark, respectively, the median stellar mass, $\log(\tilde{M}_*/M_\odot) = 9.78$, and median sSFR, $\log(\text{sSFR}/\text{yr}^{-1}) = -10.04$. In the following sections, we will study how the gas velocity dispersion distribution varies as a function of M_* and sSFR. For this reason, we split the plot in four quadrants: Q1 = low M_* – low sSFR, Q2 = low M_* – high sSFR, Q3 = high M_* – low sSFR and Q4 = high M_* – high sSFR. Q1 and Q4 contain, respectively, 7 and 8 galaxies, while Q2 and Q3 contain 14 objects.

2.4 Binning and warm gas

We binned the gas particles in each galactic cube on a 2D spatial (+1D depth) grid of pixels with linear size 2 kpc (15 pixels per cubic side), which is comparable to the effective resolution of SAMI after accounting for a typical AAT seeing of 2.1 arcsec.⁷ To obtain SPH quantities on the grid, we followed the procedure described in section 4 of Altay & Theuns (2013). We started by extracting a buffer of additional 70 kpc per side around the central cube of volume $(30 \text{ kpc})^3$ to ensure that all the gas particles in the simulation whose 3D SPH kernels intercept one or more pixels of the grid in the two spatial directions and the cube margins in the line-of-sight direction were taken into account. Then, we assigned a truncated Gaussian kernel to each gas particle (equations 8 and 9 of Altay & Theuns 2013) and integrated it over the square pixels. Using this procedure, we calculated the density-weighted (mean) velocity, velocity dispersion and temperature along the line of sight in all the pixels.

We considered different projections. In the edge-on xz (yz) projection, the line-of-sight direction is the direction y (x) perpendicular to the xz (yz) plane. The corresponding mean velocity and velocity dispersion are, respectively, v_y and σ_y for the xz projection and v_x and σ_x for the yz projection. The velocity dispersion for the face-on projection xy is σ_z . The two top panels of Fig. 2 show examples of mean (rotation) velocity maps in the two edge-on projections created using all the gas in the cube.

SAMI observations of low-redshift galaxies with outflows are largely based on the detection of H α emitting gas at $T \sim 10^4$ K. From

now on, to better compare with these observations we will distinguish between *all gas* and *warm gas*. In an SPH simulation, the fluid conditions at any point are defined by integrating over *all* particles, weighted by their kernel. Selecting only a subset of them (e.g. only star forming or cold/hot gas) would break mass/momentum/energy conservation laws. Therefore, we define *warm gas* as pixels in a velocity/velocity dispersion/temperature map, where the density weighted gas temperature (calculated using all the particles) is in the range of $3.8 \leq \log((T_{\text{gas}})/\text{K}) \leq 4.2$. Gas with temperature around 10^4 K is usually referred to as warm to distinguish it from cold gas in molecular clouds ($T < 100$ K) and hot gas in the halo or in SN bubbles ($T > 10^5$ K), based on the model of a three-phase ISM medium (McKee & Ostriker 1977). H α emission in real galaxies is mostly from H II regions, and hence correlates strongly with SFR (Kennicutt 1998). To a good approximation, in our analysis warm pixels trace pixels with density-weighted SFR greater than zero. We introduced this temperature cut to qualitatively compare with the kinematic signatures seen in SAMI observations, without having to model complicated and uncertain radiative transfer effects.

In the middle row of Fig. 2, we plot edge-on velocity dispersion maps ($xz - \sigma_y$) for (a) all gas (left-hand panel) and (b) warm gas (right-hand panel). In (a) the velocity dispersion increases when moving away from the disc of the galaxy (in both vertical directions) and peaks at $\text{abs}(z_{\text{gas}}) \sim 9$ kpc. On the other hand, in (b) the high- σ part is completely suppressed and warm gas is mainly associated with the galactic disc.⁸ This has important consequences for our analysis. We will explore them in Sections 3.1 and 3.2.

The situation is different in the bottom two panels of Fig. 2, which show face-on velocity dispersion maps ($xy - \sigma_z$) for all gas (left-hand panel) and warm gas (right-hand panel). This time the two maps are almost identical (except for two pixels). This is due to the fact that now all the lines-of-sight pierce the disc, where warm gas dominates. The σ -maps in Fig. 2 are the base of all our analyses and we will discuss them more in the next sections.

3 SIGNATURES OF OUTFLOWS: THE VELOCITY DISPERSION DISTRIBUTION

The aim of this work is to determine whether or not current and upcoming IFS surveys can successfully identify large-scale outflows and provide meaningful constraints on the physical processes driving gas out of galaxies. For this reason, we apply observationally based analysis techniques to the simulations. In particular, in the next sections we compare with the observational investigations of SAMI galaxies with outflows presented by Ho et al. (2014) and Ho et al. (2016b). We stress that observational and numerical analyses estimate the kinematic state of the gas in two different ways. We track the motion of particles as sampled by the SPH scheme in the simulation, without including any radiative transfer effects. Instead, Ho et al. (2014, 2016b) extract kinematic information from emission line spectra of galaxies. Thus, while observations only probe ionized gas, simulations take into account all the gas in the galactic halo. To facilitate the comparison, we therefore introduced in the previous section the definition of warm gas that we will use throughout the paper.

Ho et al. (2014) studied the nature of a prototypical low redshift isolated disc galaxy with outflows: SDSS J090005.05+000446.7

⁶ Note that a galaxy with $M_* = 10^9 M_\odot$ in *Recal-L025N0752* contains more than 4.4×10^3 star particles.

⁷ In Appendix A, we will explore the impact of cube size (30 and 60 kpc) and grid resolution (2 and 3 kpc) on our results.

⁸ We stress again that the map in (b) is the map in (a) with only pixels fulfilling the condition $3.8 \leq \log((T_{\text{gas}})/\text{K}) \leq 4.2$ included.




Figure 2. Top row: examples of mean (rotation) velocity maps created using all the gas in the cube. Left-hand panel: edge-on xz projection – mean v_y . Right-hand panel: edge-on yz projection – mean v_x . Middle row: gas velocity dispersion maps in the edge-on xz projection – σ_y . Left-hand panel: *all gas*. Right-hand panel: *warm gas*, that is only pixels where $3.8 \leq \log((T_{\text{gas}})/\text{K}) \leq 4.2$ (see Section 2.4). Warm gas is clearly associated with the galactic disc and virtually absent when moving away from the galaxy plane, where the all gas σ_y -map peaks. Bottom row: gas velocity dispersion maps in the face-on xy projection – σ_z . Left-hand panel: *all gas*. Right-hand panel: *warm gas*. Now, all the lines-of-sight pierce the disc (where warm gas dominates) and the two maps are almost identical.

(SDSS J0900, $z = 0.05386$). Its emission line spectrum was decomposed using the spectral fitting pipeline LZIFU (Ho et al. 2016a), a likelihood ratio test and visual inspection. Emission lines were modelled as Gaussians composed of up to three kinematic components with small, intermediate and high velocity dispersion relative to each other (i.e. from narrow to broad features). Fig. 6 of Ho et al. (2014) shows the velocity dispersion distribution of SDSS J0900. The statistically prominent narrow component peaks at $\sim 40 \text{ km s}^{-1}$ and is associated with the (rotationally supported) disc of the galaxy. More interestingly, the σ -distribution extends to very high values (450 km s^{-1}) with the broad kinematic component peaking at $\sim 300 \text{ km s}^{-1}$. The authors argue that this high- σ component traces shock excited emission in biconical outflows, likely driven by starburst activity.

3.1 All gas versus warm gas

Following Ho et al. (2014), we begin our analysis by investigating the velocity dispersion distribution of the simulated galaxies. Throughout the paper, we adopt the following procedure. Using σ -maps like those shown in the bottom four panels of Fig. 2, we first calculate the histogram of the pixelated velocity dispersion for each galaxy (i.e. the fraction of pixels per velocity dispersion bin), where the pixel size is 2 kpc, the upper limit is the maximum σ of the entire sample (that changes depending on the projection and if all gas or warm gas is considered) and the bin size is always 20 km s^{-1} . Then, we stack these histograms and normalize by the number of galaxies to obtain the final *pixelated velocity dispersion (probability) distribution* and its associated Poissonian errors.

In Fig. 3, we examine the differences between the pixelated velocity dispersions calculated using all gas and warm gas in different projections for all the 43 simulated galaxies. In the face-on (xy view) projection, the σ_z -distributions of all gas (blue squares and dot-dashed line) and warm gas (orange crosses and long-dashed line) are very similar, with the highest fractions at low σ_z and a declining trend at larger velocity dispersions and share the same $\max(\sigma_z) = 201.31 \text{ km s}^{-1}$. The only difference is that the all gas distribution shows slightly larger statistics at high σ_z . According to the bottom panels of Fig. 2, this is not surprising. When the lines of sight in different pixels pass through the galactic disc, particles in the warm gas regime are in the majority and dominate the σ_z -maps.

On the other hand, the edge-on (xz view) σ_y -distribution for all gas (black diamonds and solid line, $\sigma_{y,\max} = 211.08 \text{ km s}^{-1}$) is shifted to higher velocity dispersions than the warm gas distribution (red triangles and short dashed line, $\sigma_{y,\max} = 169.29 \text{ km s}^{-1}$), which has a more prominent peak at 30 km s^{-1} and then rapidly drops to lower fractions at high σ_y . The reasons for this are mentioned in Section 2.1 and highlighted by the two middle panels of Fig. 2. In our simulated disc galaxies, warm gas traces the disc and is virtually absent when moving away from the galaxy plane. In Section 3.3, we will show how the extraplanar velocity dispersion is dominated by outflowing gas. Therefore, the lack of warm gas outside the disc is a direct consequence of the thermal stellar feedback implemented in EAGLE that heats outflowing particles up to a temperature higher than the warm range ($T \sim 10^4 \text{ K}$). Galactic winds in our simulations are mostly hot ($T > 10^5 \text{ K}$) and, compared to observed galaxies, may entrain insufficient gas with $T < 10^5 \text{ K}$. Note that such high-temperature gas would not be visible in SAMI observations.

This issue with EAGLE was already noted by Turner et al. (2016) in a study of the $z \approx 3.5$ intergalactic medium and has important implications for our work too. A direct comparison with $H\alpha$ -based SAMI observations should be done using warm gas (since $H\alpha$ emit-




Figure 3. Pixelated velocity dispersion probability distributions (i.e. the fraction of pixels – with pixel size = 2 kpc – per velocity dispersion bin) calculated using all gas and warm gas in different projections. The bin size is 20 km s^{-1} . Black diamonds + solid line and red triangles + short dashed line: all gas and warm gas, respectively, in the edge-on xz projection – σ_y . Blue squares + dot-dashed line and orange crosses + long-dashed line: all gas and warm gas, respectively, in the face-on xy projection – σ_z . Each line was created by stacking the histograms of all the 43 galaxies in the simulated sample. Errors are Poissonian. Since in the face-on projection the lines-of-sight in different pixels always pierce the galactic disc, where warm gas dominates, the all gas and warm gas σ_z -distributions are very similar (see the bottom panels of Fig. 2). In the edge-on projection, the σ_y -distribution for all gas is shifted to higher velocity dispersions than the warm gas distribution, which is associated with the galactic disc and therefore has a more prominent peak at low $\sigma_y = 30 \text{ km s}^{-1}$ (cf. the two middle panels of Fig. 2).

ting gas has a temperature $T \sim 10^4 \text{ K}$). However, the paucity of such gas in the outflows of our simulated galaxies could lead to misleading results. Specifically, in edge-on projections, underestimation of the outflowing gas mass/incidence of galactic winds (that may be there but just too hot to be detected in $H\alpha$) and poor sampling of the extraplanar gas. In the next section, we will show an example of this problem.

3.2 Disc component and off-plane gas

We focus on the difference between gas in the disc and extraplanar gas. To do so, we take the edge-on σ_y -maps (xz view) and restrict the number of pixels in the direction perpendicular to the disc plane by applying various vertical cuts. The resulting pixelated velocity dispersion distributions (including Poissonian errors) are shown in Fig. 4. The two panels refer to all gas (left) and warm gas (right).

In the left-hand panel, when all gas and only pixels with $\text{abs}(z) < 3 \text{ kpc}$ (black filled triangles and solid line) are included,⁹ the distribution shows a sizeable peak at $\sigma_y = 30 \text{ km s}^{-1}$ and then quickly declines to low fractions. With this pixel selection, we

⁹ Here and throughout the paper, the vertical cuts are considered from the edge of the pixels, not the centre.




Figure 4. Pixelated velocity dispersion probability distributions (cf. Fig. 3 and the beginning of Section 3.1) calculated by assuming different cuts in the z -direction of the edge-on (xz view) σ_y -maps (with pixel size = 2 kpc) to separate the galactic disc component from the extraplanar one. Left-hand panel: all gas. Right-hand panel: warm gas. Black filled triangles and solid line, (internal) pixels with $\text{abs}(z) < 3$ kpc. Red filled inverted triangles and dashed line (external) pixels with $\text{abs}(z) > 3$ kpc. Orange diamonds and triple dot-dashed line, (external) pixels with $\text{abs}(z) > 5$ kpc. Errors are Poissonian. In the all gas case, excluding the galactic disc shifts the σ_y -distribution to larger velocity dispersions. In the warm gas case, the off-plane distributions are poorly sampled and only marginally different from the disc 1 due to the scarcity of extraplanar gas at $T \sim 10^4$ K.

are targeting only a thin layer of gas in the edge-on galactic discs. Red filled inverted triangles and the dashed line represent the complementary distribution calculated using only pixels with $\text{abs}(z) > 3$ kpc. In this case, the distribution is shifted to larger σ -values than before, while the low- σ part is greatly reduced. This demonstrates that the low- σ peak is indeed associated mainly with the galactic disc, in qualitative agreement with Ho et al. (2014). In the left-hand panel of Fig. 4, we also show the velocity dispersion distribution (for all gas) calculated using only pixels with $\text{abs}(z) > 5$ kpc (orange diamonds and triple dot-dashed lines). The low- σ peak and high- σ tail become, respectively, slightly less and more important when moving further away from the galactic disc, supporting our previous conclusion.

The right-hand panel of Fig. 4 illustrates how using only warm gas can be misleading, in the framework of EAGLE simulations. All three distributions are very similar (despite the fact that they probe rather different environments) and more noisy at $\sigma_y > 50$ km s $^{-1}$ than the corresponding distributions for all gas. In the edge-on warm σ_y -maps, there are only a few pixels with $\text{abs}(z) > 3$ and (especially) 5 kpc; therefore, poor sampling affects the results in these two cases. Considering only warm gas in EAGLE would lead to the wrong conclusion that planar and extraplanar gas components are kinematically similar. This is a consequence of the thermal implementation of stellar feedback that produces hot outflows. When all gas (warm & hot) is considered, the extraplanar (mainly hot) gas is kinematically clearly distinct from the (mainly warm) disc (the left-hand panel of Fig. 4).

In the rest of the paper, whenever possible and appropriate (e.g. to study face-on velocity dispersion distributions or the impact of general galactic properties like M_* and sSFR), we will show results obtained using warm gas. However, including all gas will be necessary to ensure a robust description of galactic winds and outflow signatures (see e.g. Section 5).

3.3 Outflows

In the previous section, we have demonstrated how the low- σ part of the edge-on velocity dispersion distribution is associated with the galactic disc. Now, we study the origin of the high- σ tail. In the xz edge-on projection, we consider a pixel of the σ -map as *outflow dominated* if the density-weighted vertical velocity of its gas particles, $\langle v_z \rangle$, is positive in the semi-plane with $z_{\text{gas}} > 0$ kpc or negative in the negative z_{gas} semi-plane (i.e. if the gas particles contributing to the pixel are predominantly moving away from the galactic plane). Otherwise, a pixel is flagged as *non-outflow dominated*.¹⁰ The corresponding σ_y -distributions are shown in Fig. 5. Errors are Poissonian.

The non-outflow dominated σ -distribution (black diamonds and solid line) resembles the $\text{abs}(z) < 3$ kpc distribution (i.e. associated with the galactic disc) visible in the left-hand panel of Fig. 4 (black filled triangles and solid line). With respect to these two diagrams, the outflow dominated σ -distribution of Fig. 5 (red triangles and dashed line) is shifted to higher velocity dispersions and has a more statistically prominent high- σ tail (in agreement with the $\text{abs}(z) > 3$ and 5 kpc distributions of Fig. 4). When only extraplanar gas is considered (i.e. pixels with $\text{abs}(z) > 3$ kpc), we find that in 42 out of 43 simulated galaxies, the number of outflow dominated pixels is greater than the number of non-outflow dominated pixels. On average, this excess is a factor of ~ 3.2 times and can be up to > 15 times.

Our results are qualitatively consistent with the observations of Ho et al. (2014): in low-redshift disc galaxies, the low- σ component of the velocity dispersion distribution is associated with the (rotationally supported) disc, while the high- σ component mainly

¹⁰ We mask pixels in the galactic plane (i.e. those with $-1 < z_{\text{gas}}/\text{kpc} < 1$), since their outflowing/non-outflowing status is undefined.




Figure 5. Pixelated velocity dispersion probability distributions (cf. Fig. 3 and the beginning of Section 3.1) for outflow dominated (red triangles and dashed line) and non-outflow dominated (black diamonds and solid line) pixels. Errors are Poissonian and we consider all gas in the edge-on xz projection $-\sigma_y$. The velocity dispersion distribution based on outflow dominated pixels is more prominent at high σ .

traces extraplanar, outflowing gas. In the case of strong disc–halo interactions through galactic winds, the velocity dispersion of the extraplanar gas is broadened (up to 300 km s^{-1} in the extreme case of M82) by both the turbulent motion of the outflowing gas and line splitting caused by emissions from the approaching and receding sides of the outflow cones (Ho et al. 2016b, and references therein).

There is an important caveat to consider here. In this work, outflowing material includes both particles that are actually leaving their host galaxy and particles that will eventually stop and fall back to the disc. At this stage, our numerical analysis is not able to differentiate between these two components (but this also applies to observations). Theoretical predictions on how much gas actually escapes from galaxies are crucial, since the escaping mass is very hard to measure observationally (Bland-Hawthorn & Cohen 2003; Bland-Hawthorn et al. 2007). Recent simulations run by different groups indicate that wind recycling becomes particularly important at $z < 1$ and galaxies of all masses reaccrete more than 50 per cent of the expelled gas (e.g. Oppenheimer et al. 2010; Nelson et al. 2015; Christensen et al. 2016; Anglés-Alcázar et al. 2017). This point will be addressed in an upcoming paper (Crain et al. in prep). Note that the thermal/buoyant winds in our EAGLE discs will allow particles without enough velocity/thermal energy to escape to float up to the top of the galactic halo (Bower et al. 2017).

4 IMPACT OF STELLAR MASS, SPECIFIC SFR, SFR SURFACE DENSITY AND GAS TEMPERATURE

In this section, we study the impact of different galactic properties on the overall shape of the velocity dispersion distribution. Since we do not focus primarily on the high- σ tail associated with outflows, results are presented for warm gas to better compare with the observational analysis of Ho et al. (2014, 2016b). We begin with stellar mass and the sSFR. Fig. 6 shows the result: the edge-on

xz projection $-\sigma_y$ in the left-hand panel and the face-on xy projection $-\sigma_z$ in the right-hand panel (errors are Poissonian). We divided our galaxies according to the four M_* –sSFR quadrants in the bottom right-hand panel of Fig. 1 (the same colour code applies).

A clear trend with stellar mass is visible in both panels, while the sSFR appears to have a secondary effect. It is interesting to note how, especially in the edge-on projection (left-hand panel), the velocity dispersion distribution of low-mass galaxies (black diamonds + solid line and red triangles + dashed line, respectively, associated with Q1 and Q2) declines shortly after the peak at 30 km s^{-1} (associated with the disc) and drops to zero already at 70 km s^{-1} . The predominance of the disc component in Q1 and Q2 is present also when all gas distributions (not shown here) are used. The σ -distributions of galaxies with high M_* (blue squares + dot-dashed line and orange crosses + triple dot-dashed line, respectively, associated with Q3 and Q4) are more extended, and prominent at high σ , than those of low-mass galaxies (regardless of the range in sSFR). At $\sigma < 100 \text{ km s}^{-1}$, this is due to the fact that in the synthetic sample warm gas mainly traces the galactic disc and objects in Q3 and Q4 are generally bigger. Due to the SFR– M_* relation and the fact that in EAGLE there is a direct connection between SFR and stellar feedback, these objects also have higher outflowing activities than galaxies in Q1 and Q2. Despite the lack of warm gas in EAGLE’s galactic winds, this causes the broadening of the σ -distributions to higher velocity dispersion.

Our simulated face-on distributions, with $\max(\sigma_z) = 201.31 \text{ km s}^{-1}$, do not extend as far as the velocity dispersion diagram of the SDSS J0900 galaxy in Ho et al. (2014), with $\max(\sigma_z) \sim 450 \text{ km s}^{-1}$. This might be in part due to the fact that SDSS J0900 is more massive, $\log(M_*/M_\odot) = 10.8$, and has a higher SFR ($\sim 5\text{--}15 M_\odot \text{ yr}^{-1}$, depending on the adopted SFR indicator) than objects in our synthetic sample, but could also indicate that the effect of EAGLE stellar feedback on gas kinematics is too weak. Simulated galaxies in Q2, Q3 and Q4 have distributions that reach $\sigma_z > 100 \text{ km s}^{-1}$,¹¹ which is the starting point of the broad kinematic component associated with outflowing gas in SDSS J0900.

4.1 SFR surface density

Ho et al. (2016b) found that, on average, wind galaxies have higher SFR surface densities than those without strong wind signatures. We checked this result with our simulated sample in Fig. 7. Following Ho et al. (2016b), the SFR surface density is defined as $\Sigma_{\text{SFR}} = \text{SFR}/(2\pi r_{50}^2)$, where SFR is the total SFR of the object as determined by `SUBFIND` and r_{50} is the radius within which half of the galaxy stellar mass is included. The top panel of Fig. 7 shows the $\Sigma_{\text{SFR}} - M_*$ relation of EAGLE galaxies. As for SFR and M_* , the two quantities are positively correlated. The vertical and horizontal dashed lines mark, respectively, the median stellar mass, $\log(\bar{M}_*/M_\odot) = 9.78$, and median SFR surface density, $\log(\bar{\Sigma}_{\text{SFR}}/[M_\odot \text{ yr}^{-1} \text{ kpc}^{-2}]) = -2.77$. We divided the plot in four sectors: S1 = low M_* – low Σ_{SFR} (16 objects), S2 = low M_* – high Σ_{SFR} (5 objects), S3 = high M_* – low Σ_{SFR} (6 objects) and S4 = high M_* – high Σ_{SFR} (16 objects). The corresponding velocity dispersion distributions are shown in the bottom panels of Fig. 7: warm gas on the left and all gas on the right (we only consider the edge-on xz projection $-\sigma_y$).

¹¹ In the edge-on projection, only galaxies with high M_* (Q3 and Q4) have distributions with $\max(\sigma_y) > 100 \text{ km s}^{-1}$.




Figure 6. Pixelated velocity dispersion probability distributions (cf. Fig. 3 and the beginning of Section 3.1) for galaxies in the four M_* – sSFR quadrants defined in the bottom right-hand panel of Fig. 1: Q1 = low M_* – low sSFR, Q2 = low M_* – high sSFR, Q3 = high M_* – low sSFR and Q4 = high M_* – high sSFR. Left-hand panel: edge-on xz projection – σ_y . Right-hand panel: face-on xy projection – σ_z . Errors are Poissonian and we consider only warm gas. In general, galaxies with higher M_* present a more extended σ -distribution, while the sSFR has a secondary effect with respect to stellar mass.

We start by considering the warm gas case (the left-hand panel of Fig. 7). Trends are similar to those of the left-hand panel of Fig. 6. At low masses (S1 and S2), the velocity dispersion distributions of galaxies with low and high Σ_{SFR} are almost identical (black diamonds + solid line and red triangles + dashed line), with a narrow peak at 30 km s^{-1} . These galaxies have relatively low SFRs and weak outflowing activities; therefore, warm gas mainly traces their galactic discs (of similar size). The probability distributions of high-mass galaxies (blue squares + dot-dashed line and orange crosses + triple dot-dashed line, respectively associated with S3 and S4) are shifted to larger values than those of low-mass galaxies. As discussed in the previous section, part of the shift is driven by the increase in stellar mass, but a correlation with the SFR surface density is now visible (a more extended high- σ tail for objects in S4 with high Σ_{SFR}).

Patterns are different in the all gas case (the right-hand panel of Fig. 7). A trend with stellar mass is still present (black and red versus blue and orange points and lines), but, at fixed M_* , galaxies with high Σ_{SFR} give rise to a σ -distribution shifted to larger velocity dispersions compared to galaxies with low Σ_{SFR} (red and orange versus black and blue points and lines). As in the observations of Ho et al. (2016b), this result, only partially visible before due to the lack of warm gas in the outflows of EAGLE galaxies, indicates that the SFR surface density correlates with the outflowing activity even when Σ_{SFR} is rather low, as it is the case of our simulated galaxies (we will explore the correlation in more detail in Section 5). According to Heckman (2002), starburst-driven winds are observed to be ubiquitous in galaxies with $\log(\Sigma_{\text{SFR}}/[M_{\odot} \text{ yr}^{-1} \text{ kpc}^{-2}]) > -1$ (see also the results of Sharma et al. 2017). In our sample, $\log(\Sigma_{\text{SFR,max}}/[M_{\odot} \text{ yr}^{-1} \text{ kpc}^{-2}]) = -1.95$, almost a dex lower.¹²

¹² In Ho et al. (2016b), winds are seen at $-3 \lesssim \log(\Sigma_{\text{SFR}}/[M_{\odot} \text{ yr}^{-1} \text{ kpc}^{-2}]) \lesssim -1.5$.

4.2 The role of gas temperature

Since the predictive power of realistic numerical simulations allows us to study the effect of additional galactic properties, which are usually hard to measure observationally, we looked for a way to better relate the shape of the velocity dispersion distribution to feedback processes. In EAGLE, stellar feedback is implemented thermally, and we found that temperature is a good proxy to distinguish low- and high- σ parts in our simulated galaxies. The average temperature histogram of gas particles inside cubes of volume $(30 \text{ kpc})^3$ centred on each simulated galaxy splits into two regions: the bulk of particles with $T < 10^5 \text{ K}$ and a tail of particles with $T \geq 10^5 \text{ K}$ (see the left-hand panel of Fig. 8). For this reason, we divided pixels in the velocity dispersion distribution, where the density-weighted gas temperature is above and below 10^5 K . The result is visible in the right-hand panel of Fig. 8 (we consider all gas in the edge-on xz projection – σ_y , errors are Poissonian). The condition on temperature produces two very different probability distributions. When pixels with $T < 10^5 \text{ K}$ are selected (black diamonds and solid line), the distribution peaks at $\sigma_y = 30 \text{ km s}^{-1}$, then quickly drops to low fractions. On the other hand, pixels with $T \geq 10^5 \text{ K}$ give rise to a distribution shifted to larger velocity dispersions and where the low- σ section is less prominent (red triangles and dashed line). These trends, which we find are also visible in the face-on xy projection – σ_z , support the results of the previous sections (see in particular the left-hand panel of Figs 4 and 5).

Thus, EAGLE simulations of low-redshift disc galaxies indicate a direct correlation between the thermal state of the gas and its state of motion as described by the velocity dispersion distribution:

- (i) Low- σ peak \Leftrightarrow galactic disc/gas with $T < 10^5 \text{ K}$;
- (ii) High- σ tail \Leftrightarrow outflows/gas with $T \geq 10^5 \text{ K}$.

The real picture is certainly more complicated than this. For example, blobs of cold gas at relatively high density could be entrained in hot, diffuse winds (Veilleux et al. 2005; Cooper et al. 2008, 2009). Despite the simplifications made in our analysis, the predicted




Figure 7. Top panel: relation between SFR surface density, Σ_{SFR} , and M_{\star} for our simulated galaxies. $\Sigma_{\text{SFR}} = \text{SFR}/(2\pi r_{50}^2)$, where SFR is the total SFR and r_{50} is the radius within which half of the galaxy stellar mass is included. The plot is divided in four sectors: S1 = low M_{\star} – low Σ_{SFR} , S2 = low M_{\star} – high Σ_{SFR} , S3 = high M_{\star} – low Σ_{SFR} and S4 = high M_{\star} – high Σ_{SFR} (see Section 4.1). Bottom panels: pixelated velocity dispersion probability distributions (cf. Fig. 3 and the beginning of Section 3.1) for galaxies in the four sectors defined in the top panel. Errors are Poissonian. We only consider the edge-on xz projection – σ_y . Left-hand panel: warm gas. As in the previous section, a trend with stellar mass is visible. Right-hand panel: all gas. At fixed M_{\star} , galaxies with high Σ_{SFR} give rise to a σ -distribution shifted to larger velocity dispersions compared to galaxies with low Σ_{SFR} .

correlation between EAGLE’s thermal/buoyant outflows and high temperature gas can be very useful to guide and interpret real observations.

5 SIGNATURES OF WINDS: GAS KINEMATICS IN EAGLE AND SAMI GALAXIES

Ho et al. (2016b) proposed an empirical identification of wind-dominated SAMI galaxies. In this section, we apply the same methodology to our simulated sample. The authors defined two dimensionless quantities to measure the (ionized gas) extraplanar

velocity dispersion and asymmetry of the velocity field. The first quantity is the velocity dispersion to rotation ratio parameter:

$$\eta_{50} = \sigma_{50}/v_{\text{rot}}, \quad (1)$$

where σ_{50} is the median velocity dispersion of all pixels outside \bar{r}_e (the r -band effective radius increased by approximately 1 arcsec to reduce the effect of beam smearing) with signal-to-noise in $\text{H}\alpha$ – $\text{S/N}(\text{H}\alpha)$ – greater than 5. v_{rot} is the maximum rotation velocity measured from the pixels along the optical major axis (for galaxies without sufficient spatial coverage, they used the stellar




Figure 8. Left-hand panel: average temperature distribution of gas particles inside cubes of linear size 30 kpc centred on each simulated galaxy. Two distinct regions are visible in the gas temperature histogram: the bulk of particles with $T < 10^5$ K and a tail of particles with $T \geq 10^5$ K. Right-hand panel: effect of gas temperature on the pixelated velocity dispersion probability distribution (cf. Fig. 3 and the beginning of Section 3.1) of galaxies. Black diamonds and solid line: pixels where the density-weighted gas temperature is $T < 10^5$ K. Red triangles and dashed line: pixels with $T \geq 10^5$ K. Errors are Poissonian and we only consider the edge-on xz projection $-\sigma_y$. Pixels with temperature $T < 10^5$ K trace the galactic disc (low σ), while those with $T \geq 10^5$ K are associated with higher σ (i.e. extraplanar, outflowing gas).

mass Tully–Fisher relation to infer v_{rot} . The second quantity is the asymmetry parameter:

$$\xi = \text{std} \left(\frac{v_{\text{gas}} - v_{\text{gas,flipped}}}{\sqrt{\text{Err}(v_{\text{gas}})^2 + \text{Err}(v_{\text{gas,flipped}})^2}} \right), \quad (2)$$

where std = standard deviation. To obtain ξ , the authors first flipped the line-of-sight velocity map over the galaxy major axis, $v_{\text{gas,flipped}}$, and then subtracted the flipped map from the original one, v_{gas} . $\text{Err}(v_{\text{gas}})$ and $\text{Err}(v_{\text{gas,flipped}})$ are the corresponding 1σ error maps from LZIFU. The standard deviation is again calculated taking into account only pixels outside \bar{r}_e with $S/N(\text{H}\alpha) > 5$.

Ho et al. (2016b) used η_{50} and ξ to quantify the strength of disc–halo interactions and to distinguish galactic winds from extended diffuse ionized gas (eDIG) in a sample of 40 low-redshift disc galaxies. Since galactic winds both perturb the symmetry of the extraplanar gas velocity and increase the extraplanar emission line widths, they should show high ξ and high η_{50} . On the other hand, eDIG is more closely tied to the velocity field of the galaxy and therefore should result in low ξ and low η_{50} .

We calculated η_{50} and ξ for our simulated galaxies and plot them (dots and squares) along with the observational data (black/red crosses) in Fig. 9. We remind the reader that there are some differences between the two analyses. The underlying assumptions are the same (i.e. regular, not warped discs and rotation maps, exclusion of mergers and systems undergoing major interactions) but, for example, $\text{Err}(v_{\text{gas}})$ and $\text{Err}(v_{\text{gas,flipped}})$ in equation (2) are undefined in our analysis of EAGLE galaxies, since we rely on the SPH scheme to directly determine the kinematic state of the gas, without performing any emission line fitting. Instead, to obtain an estimate of the noise consistent with SAMI data, we fit a polynomial to Ho et al. (2016b)’s $\text{Err}_{\text{obs}}(v_{\text{gas}}) - z$ (kpc) scatter plot and then add the observational noise to the simulated velocity maps. Note that the

error on v_{gas} increases with the distance from the galaxy plane because the S/N of extraplanar $\text{H}\alpha$ emission is lower than that of $\text{H}\alpha$ gas in the disc. Furthermore, observations only consider ionized gas, while we take into account all (warm + hot) gas in the galactic cubelet to better sample any outflowing activity (see Sections 3.1 and 3.2). Despite these differences, the range in η_{50} and ξ is similar in simulations and observations.

Ho et al. (2016b) empirically defined as *wind-dominated* those galaxies with $\eta_{50} > 0.3$ and $\xi > 1.8$. These limits are visible in the left-hand panel of Fig. 9 as the vertical and horizontal black dotted lines. Accordingly, red \times symbols in the figure represent wind-dominated SAMI galaxies (15 out of 40), while black \times symbols are associated with (25) observed objects without strong wind signatures. Amongst the EAGLE galaxies, just one object has $\eta_{50} < 0.3$ (and only in the yz projection value). Although this would be consistent with a wind-dominated galaxy sample, the range in ξ does not support this conclusion. The mean asymmetry parameter is 1.63 (below the threshold of Ho et al. 2016b) and only five discs have $\xi > 1.8$ in both projections.

We are interested in studying the interdependency between η_{50} , ξ and relevant galactic properties. As for the observational sample, the Spearman rank correlation test indicates no significant correlation between the two parameters: $\rho = 0.12$ with a significance of 0.27. Ho et al. (2016b) argue that if winds are the only mechanism disturbing the extraplanar gas, then a trend between η_{50} and ξ should be expected. The fact that both works fail to find a significant correlation suggests that, when applied to current data and simulations, the $\xi - \eta_{50}$ plot might not be accurate enough for the identification of wind-dominated galaxies. Ho et al. (2016b) speculate that gas accreted on to galaxies through satellite accretion would cause a large velocity asymmetry of the extraplanar gas without affecting much the off-plane velocity dispersion (i.e. large ξ and small η_{50}), and therefore complicate the interpretation of the $\xi - \eta_{50}$ plot




Figure 9. Left-hand panel: asymmetry parameter ξ versus velocity dispersion to rotation ratio parameter η_{50} . Dots: simulated edge-on xz projection. Squares: simulated edge-on yz projection. Synthetic data are colour coded according to the SFR surface density of the parent galaxy, $\Sigma_{\text{SFR}} = \text{SFR}/(2\pi r_{50}^2)$. The vertical and horizontal dotted lines mark the observational limits above which galaxies show strong disc–halo interactions according to Ho et al. (2016b), $\eta_{50} > 0.3$ and $\xi > 1.8$. Crosses: observational SAMI data, where red \times symbols represent wind-dominated galaxies and black \times symbols represent galaxies without strong wind signatures. Right-hand panel: correlation between the asymmetry parameter ξ and Σ_{SFR} . Grey dots and squares: simulated galaxies in the edge-on xz and yz projections, respectively. Crosses: observational data from Ho et al. (2016b). In both panels, the range of the simulated parameters (determined using all gas) is broadly consistent with the observations. A clear positive $\xi - \Sigma_{\text{SFR}}$ correlation is visible in both EAGLE and SAMI data.

in terms of galactic winds and eDIG. We saw in Section 3.3 how the extraplanar gas distribution of EAGLE objects is dominated by outflows (the ratio of outflow to non-outflow dominated pixels is on average ~ 3.2). Unfortunately, this does not lead to a significant $\xi - \eta_{50}$ correlation in the simulated sample.

However, Fig. 9 highlights a different trend within EAGLE and SAMI data. In the left-hand panel, simulations are colour coded according to the SFR surface density of the parent galaxy, $\Sigma_{\text{SFR}} = \text{SFR}/(2\pi r_{50}^2)$. In general, objects with low/high ξ have low/high Σ_{SFR} (i.e. bluish points are below reddish points). This positive correlation is even more visible in the right-hand panel of Fig. 9, where we plot ξ as a function of Σ_{SFR} . The Spearman rank correlation test indicates a significant correlation between the two parameters both in simulations¹³ (grey dots and squares, $\rho = 0.67$ with a significance of $\sim 10^{-6}$) and observations¹⁴ (black/red crosses, $\rho = 0.56$ with a significance of 1.6×10^{-4}). Since the asymmetry parameter marks the incidence of galactic winds in disc galaxies, this result is in qualitative agreement with Section 4.1 and the conclusions of Ho et al. (2016b): the SFR surface density correlates with outflowing activity.

At this point, it is important to remark that numerical results could be affected by statistical noise in various ways. For example, in low mass, small galaxies high asymmetry could be due to poor sampling of the extraplanar gas distribution, rather than galactic

winds. Moreover, since our discs are fairly regular, the two sets of η_{50} and ξ parameters associated with the edge-on xz and yz projections should contain the same information, and therefore be statistically similar. However, the analysis is limited by the small size of the synthetic sample (43 galaxies), which is due to the small box size of the cosmological simulation used (25 cMpc). In principle, increasing resolution and box size of the simulations will alleviate the impact of statistical noise.

Note that the position of SAMI galaxies in the $\xi - \eta_{50}$ plot can also be biased in different ways. For example, see the discussion in Ho et al. (2016b) on how, for galaxies without a direct measurement of v_{rot} , the lack of correlation between ξ and η_{50} is partially due to the scatter in the Tully–Fisher relation. Furthermore, the high asymmetry seen in some of the observed galaxies might be accentuated by inclination effects (while all the simulated galaxies are perfectly edge-on).

In summary, according to our analysis, the $\xi - \eta_{50}$ plot does not seem to provide a clear, unambiguous tool to identify wind-dominated galaxies. Although using simulations with higher resolution (and better quality observational data) could improve the results, different observables (e.g. the velocity dispersion distribution) appear to estimate the outflowing activity of star forming galaxies more accurately than ξ and η_{50} .

6 CONCLUSIONS

In this paper, we have presented an analysis of stellar feedback-driven galactic outflows based on the comparison between hydrodynamic simulations and IFS observations from the SAMI survey (Bryant et al. 2015). We have extracted cubes of 30 physical kpc around unperturbed disc galaxies from the highest resolution

¹³ For each simulated galaxy, there are two values of ξ , corresponding to the edge-on projections xz and yz . We averaged the two values into a single one to calculate the asymmetry– Σ_{SFR} correlation.

¹⁴ Ho et al. (2016b) quoted both spectral energy distribution (SED) and H α -based SFRs for their sample. Here, we use $\text{SFR}_{\text{H}\alpha}$ to calculate the observed Σ_{SFR} . We checked that our conclusions do not change when using SFR_{SED} .

cosmological simulation of the EAGLE set (Schaye et al. 2015). Our final sample includes 43 main-sequence objects with $9.02 \leq \log(M_*/M_\odot) \leq 10.76$ and $\log(\text{sSFR}/\text{yr}^{-1}) = -10.04$ (Fig. 1). We have divided each cubelet into a grid of pixel size 2 kpc (which is comparable to the effective resolution of SAMI) and created gas rotation velocity and velocity dispersion maps (Fig. 2). In our study, the terms *galactic winds* and *outflows* are synonyms that we have used to identify both gas in the process of leaving a galaxy and gas that will eventually stop and fall back to the disc.

This work is the theoretical counterpart of the observational analyses on SAMI galaxies with outflows presented in Ho et al. (2014) and Ho et al. (2016b). In the first part of the paper, we have focused on the pixelated velocity dispersion (probability) distribution as a tracer of galactic wind signatures. To better compare with SAMI observations that mainly target H α emitting gas at $T \sim 10^4$ K, we have distinguished between *all gas* and *warm gas*. The latter identifies pixels in a velocity/velocity dispersion/temperature map, where the density-weighted gas temperature (calculated using all the particles) is in the range of $3.8 \leq \log((T_{\text{gas}}/K)) \leq 4.2$. We have found that, in EAGLE galaxies, warm gas traces the disc and is virtually absent when moving away from the galaxy plane (middle two panels of Fig. 2). For this reason, the edge-on velocity dispersion for warm gas has a less prominent high- σ tail (that is mostly associated with outflows) and a lower σ_{max} than the all gas distribution, while the two face-on distributions are very similar (Fig. 3). The lack of warm gas outside the disc is a direct consequence of the thermal stellar feedback implemented in EAGLE. Galactic winds in our simulations are mostly hot (with a $T > 10^5$ K they would not be seen in SAMI observations), buoyant (rather than ballistic, cf. Bower et al. 2017) and, compared to observed galaxies, may entrain insufficient gas with $T < 10^5$ K (as pointed out also by Turner et al. 2016). Throughout the paper, whenever possible and appropriate we have performed our analysis using warm gas. However, when studying outflowing material and galactic wind signatures we have included all gas to obtain more reliable results.

We have targeted the galactic disc by taking into account only pixels with $\text{abs}(z) < 3$ kpc in the edge-on xz projection (with the disc lying in the xy plane). The σ -distribution peaks at 30 km s^{-1} and then quickly declines to low fractions. The complementary distributions (pixels with $\text{abs}(z) > 3$, 5 kpc) extend to progressively larger values and have a less prominent low- σ peak (Fig. 4). This demonstrates that the low- σ part of the velocity dispersion distribution is associated mainly with the galactic disc. On the other hand, (extraplanar) outflowing gas dominates the high- σ tail (Fig. 5). Both these results are in qualitative agreement with the observations of Ho et al. (2014).

In general, galaxies with higher stellar mass present a more extended σ -distribution (in both the edge-on and face-on projections), while the specific SFR has a secondary effect with respect to M_* (Fig. 6). At fixed stellar mass and when all gas is used, the edge-on probability distribution of galaxies with high $\Sigma_{\text{SFR}} = \text{SFR}/(2\pi r_{50}^2)$ (where r_{50} is the radius within which half of the galaxy stellar mass is included) is shifted towards larger velocity dispersions (and more extended) than the low- Σ_{SFR} one (Fig. 7). As in the SAMI observations of Ho et al. (2016b), this indicates that the SFR surface density correlates with the outflowing activity even at the low Σ_{SFR} seen in our simulated galaxies: $\log(\Sigma_{\text{SFR}}/[M_\odot \text{ yr}^{-1} \text{ kpc}^{-2}]) \leq -1.95$.

We have studied the impact of temperature on the velocity dispersion distribution and found that there is a direct correlation between the thermal state of the gas and its state of motion. Gas with temperature $T < 10^5$ K traces the low- σ galactic disc, while gas with $T \geq 10^5$ K is mainly associated with higher- σ (i.e. extraplanar, out-

flowing gas, Fig. 8). Our results imply the following relations for low-redshift disc galaxies in EAGLE:

- (i) Low- σ peak \Leftrightarrow galactic disc \Leftrightarrow gas with $T < 10^5$ K;
- (ii) High- σ tail \Leftrightarrow galactic winds \Leftrightarrow gas with $T \geq 10^5$ K.

We have applied the empirical identification of wind-dominated SAMI galaxies proposed by Ho et al. (2016b) to the simulated sample. The ranges of the two parameters used to measure the strength of disc-halo interactions, η_{50} (velocity dispersion to rotation ratio) and ξ (asymmetry of the extraplanar gas), are similar in simulations and observations, and most of EAGLE galaxies have $\eta_{50} > 0.3$ (one of the thresholds introduced by Ho et al. 2016b to define when outflows become important, the other being $\xi > 1.8$). Although this would be consistent with a wind-dominated synthetic sample, the range in ξ does not support this conclusion: only five discs have $\xi > 1.8$. Moreover, the lack of a significant correlation between η_{50} and ξ suggests that the $\xi - \eta_{50}$ plot is currently not accurate enough to provide a clear, unambiguous way to identify wind-dominated galaxies (the left-hand panel of Fig. 9). However, we have found a significant correlation between the asymmetry parameter ξ and the SFR surface density of the parent galaxy (the right-hand panel of Fig. 9) that qualitatively confirms our result that Σ_{SFR} correlates with the outflowing activity.

In Appendix A, we have tested the impact of different cube sizes and grid resolutions. Increasing the pixel size from 2 to 3 kpc has a minimum impact on the σ -distribution, while changing the cube size from 30 to 60 kpc reduces the statistical relevance of the high- σ tail (Fig. A1). Finally, in Appendix B we have tested our analysis on idealized simulations of isolated disc galaxies (Fig. B1). Results support the picture emerging from the analysis of EAGLE galaxies, where outflows are responsible for the high- σ tail of the velocity dispersion distribution (Fig. B2).

In summary, the velocity dispersion distribution has the potential to provide valuable information on the outflowing activity in galaxies. Notably, shape and extension of the high- σ tail correlate with the strength of galactic winds. The comparison with SAMI observations has highlighted a limitation of EAGLE's stellar feedback: there is a dearth of cold and warm gas in the (mostly hot) simulated galactic outflows. Our results emphasize the double benefit of comparing simulations and observations: simulations are a valuable tool to interpret IFS data, and detailed observations guide the development of more realistic simulations. The next steps are to calculate how much gas actually escapes from galaxies and probe star formation activity and galactic winds in the time domain, following thermodynamic and kinematic changes as they happen. This is where the predictive power of simulations can play a pivotal role. As pointed out by Guidi et al. (2016b), it will be important moving towards an unbiased, consistent comparison between simulated and real galaxies.

The work presented in this paper extends the investigation of Ho et al. (2014, 2016b) and contributes to placing SAMI observations of wind-dominated galaxies in a physical context. Together, these studies provide important constraints for ongoing IFS surveys and, in the longer term, will help with planning for the next-generation multiobject integral field units including HECTOR, the successor of SAMI (Lawrence et al. 2012; Bland-Hawthorn 2015; Bryant et al. 2016).

ACKNOWLEDGEMENTS

ET would like to thank Lemmy Kilmister for constant inspiration during the writing of this paper and Jeremy Mould & Paul Geil

for many insightful discussions. RAC is a Royal Society University Research Fellow. SMC acknowledges the support of an Australian Research Council Future Fellowship (FT100100457). Support for AMM is provided by NASA through Hubble Fellowship grant #HST-HF2-51377 awarded by the Space Telescope Science Institute, which is operated by the Association of Universities for Research in Astronomy, Inc., for NASA, under contract NAS5-26555. The SAMI Galaxy Survey is based on observations made at the Anglo-Australian Telescope. The Sydney-AAO Multi-object Integral field spectrograph (SAMI) was developed jointly by the University of Sydney and the AAO. The SAMI input catalogue is based on data taken from the Sloan Digital Sky Survey, the GAMA Survey and the VST ATLAS Survey. The SAMI Galaxy Survey is funded by the Australian Research Council Centre of Excellence for All-sky Astrophysics (CAASTRO), through project number CE110001020, and other participating institutions. The SAMI Galaxy Survey website is <http://sami-survey.org/>. Part of this research was done using the National Computational Infrastructure (NCI) *Raijin*-distributed memory cluster and supported by the Flagship Allocation Scheme of the NCI National Facility at the Australian National University (ANU). For the post-processing, we used the *Edward* and *Spartan* High Performance Computing (HPC) clusters at the University of Melbourne. This work also used the DiRAC Data Centric system at Durham University, operated by the Institute for Computational Cosmology on behalf of the STFC DiRAC HPC Facility (<http://dirac.ac.uk>). The DiRAC system was funded by BIS National E-Infrastructure capital grant ST/K00042X/1, STFC capital grants ST/H008519/1 and ST/K00087X/1, STFC DiRAC Operations grant ST/K003267/1 and Durham University. DiRAC is part of the National E-Infrastructure. This work was supported by STFC grant ST/L00075X/1.

REFERENCES

- Allen J. T. et al., 2015, *MNRAS*, 446, 1567
 Altay G., Theuns T., 2013, *MNRAS*, 434, 748
 Anglés-Alcázar D., Faucher-Giguère C.-A., Kereš D., Hopkins P. F., Quataert E., Murray N., 2017, *MNRAS*, 470, 4698
 Bahé Y. M. et al., 2016, *MNRAS*, 456, 1115
 Barai P. et al., 2013, *MNRAS*, 430, 3213
 Barai P., Monaco P., Murante G., Ragagnin A., Viel M., 2015, *MNRAS*, 447, 266
 Bershadsky M. A., Verheijen M. A. W., Swaters R. A., Andersen D. R., Westfall K. B., Martinsson T., 2010, *ApJ*, 716, 198
 Bland-Hawthorn J., 2015, in Ziegler B. L., Combes F., Dannerbauer H., Verdugo M., eds, *Proc. IAU Symp. 309, Galaxies in 3D across the Universe*. p. 21
 Bland-Hawthorn J., Cohen M., 2003, *ApJ*, 582, 246
 Bland-Hawthorn J., Veilleux S., Cecil G., 2007, *Ap&SS*, 311, 87
 Bland-Hawthorn J. et al., 2011, *Optics Express*, 19, 2649
 Bower R. G., Schaye J., Frenk C. S., Theuns T., Schaller M., Crain R. A., McAlpine S., 2017, *MNRAS*, 465, 32
 Brüggén M., Scannapieco E., 2016, *ApJ*, 822, 31
 Bryant J. J., Bland-Hawthorn J., Fogarty L. M. R., Lawrence J. S., Croom S. M., 2014, *MNRAS*, 438, 869
 Bryant J. J. et al., 2015, *MNRAS*, 447, 2857
 Bryant J. J. et al., 2016, in *Proc. SPIE Conf. Ser. Vol. 9908, Ground-based and Airborne Instrumentation for Astronomy VI*. SPIE, Bellingham, p. 99081F
 Bundy K. et al., 2015, *ApJ*, 798, 7
 Bustard C., Zweibel E. G., D’Onghia E., 2016, *ApJ*, 819, 29
 Cappellari M., 2016, *ARA&A*, 54, 597
 Cappellari M. et al., 2011, *MNRAS*, 413, 813
 Ceverino D., Arribas S., Colina L., Rodríguez Del Pino B., Dekel A., Primack J., 2016, *MNRAS*, 460, 2731
 Chabrier G., 2003, *PASP*, 115, 763
 Chisholm J., Tremonti C. A., Leitherer C., Chen Y., Wofford A., 2016a, *MNRAS*, 457, 3133
 Chisholm J., Tremonti Christy A., Leitherer C., Chen Y., 2016b, *MNRAS*, 463, 541
 Christensen C. R., Davé R., Governato F., Pontzen A., Brooks A., Munshi F., Quinn T., Wadsley J., 2016, *ApJ*, 824, 57
 Cicone C., Maiolino R., Marconi A., 2016, *A&A*, 588, A41
 Cooper J. L., Bicknell G. V., Sutherland R. S., Bland-Hawthorn J., 2008, *ApJ*, 674, 157
 Cooper J. L., Bicknell G. V., Sutherland R. S., Bland-Hawthorn J., 2009, *ApJ*, 703, 330
 Crain R. A. et al., 2015, *MNRAS*, 450, 1937
 Croom S. M. et al., 2012, *MNRAS*, 421, 872
 Dale J. E., 2015, *New A Rev.*, 68, 1
 Dalla Vecchia C., Schaye J., 2012, *MNRAS*, 426, 140
 Dolag K., Borgani S., Murante G., Springel V., 2009, *MNRAS*, 399, 497
 Fogarty L. M. R. et al., 2012, *ApJ*, 761, 169
 Furlong M. et al., 2017, *MNRAS*, 465, 722
 Girichidis P. et al., 2016, *MNRAS*, 456, 3432
 Green A. W. et al., 2017, preprint ([arXiv:1707.08402](https://arxiv.org/abs/1707.08402))
 Guidi G., Casado J., Ascasibar Y., Galbany L., Sánchez-Blázquez P., Sánchez S. F., Fabián Rosales-Ortega F., Scannapieco C., 2016a, preprint ([arXiv:1610.07620](https://arxiv.org/abs/1610.07620))
 Guidi G., Scannapieco C., Walcher J., Gallazzi A., 2016b, *MNRAS*, 462, 2046
 Hayward C. C., Hopkins P. F., 2017, *MNRAS*, 465, 1682
 Heckman T. M., 2002, in Mulchaey J. S., Stocke J. T., eds, *ASP Conf. Ser. Vol. 254, Extragalactic Gas at Low Redshift*. Astron. Soc. Pac., San Francisco, p. 292
 Heckman T. M., Alexandroff R. M., Borthakur S., Overzier R., Leitherer C., 2015, *ApJ*, 809, 147
 Hobbs A., Read J., Power C., Cole D., 2013, *MNRAS*, 434, 1849
 Ho I.-T. et al., 2014, *MNRAS*, 444, 3894
 Ho I.-T. et al., 2016a, *Ap&SS*, 361, 280
 Ho I.-T. et al., 2016b, *MNRAS*, 457, 1257
 Kacprzak G. G., Muzahid S., Churchill C. W., Nielsen N. M., Charlton J. C., 2015, *ApJ*, 815, 22
 Katz N., Weinberg D. H., Hernquist L., 1996, *ApJS*, 105, 19
 Keller B. W., Wadsley J., Couchman H. M. P., 2015, *MNRAS*, 453, 3499
 Kennicutt R. C., Jr., 1998, *ARA&A*, 36, 189
 Kim C.-G., Ostriker E. C., Raiceanu R., 2017, *ApJ*, 834, 25
 Lawrence J. et al., 2012, in *Proc. SPIE Conf. Ser. Vol. 8446, Ground-based and Airborne Instrumentation for Astronomy IV*. SPIE, Bellingham, p. 844653
 Leitherer C., Chandar R., Tremonti C. A., Wofford A., Schaefer D., 2013, *ApJ*, 772, 120
 Leslie S. K. et al., 2017, preprint ([arXiv:1707.03879](https://arxiv.org/abs/1707.03879))
 Li M., Ostriker J. P., Cen R., Bryan G. L., Naab T., 2015, *ApJ*, 814, 4
 Li M., Bryan G. L., Ostriker J. P., 2017, *ApJ*, 841, 101
 Martin C. L., Shapley A. E., Coil A. L., Kornei K. A., Bundy K., Weiner B. J., Noeske K. G., Schiminovich D., 2012, *ApJ*, 760, 127
 Martizzi D., Fielding D., Faucher-Giguère C.-A., Quataert E., 2016, *MNRAS*, 459, 2311
 Mashchenko S., Wadsley J., Couchman H. M. P., 2008, *Science*, 319, 174
 McKee C. F., Ostriker J. P., 1977, *ApJ*, 218, 148
 Meiksin A., 2016, *MNRAS*, 461, 2762
 Muratov A. L., Kereš D., Faucher-Giguère C.-A., Hopkins P. F., Quataert E., Murray N., 2015, *MNRAS*, 454, 2691
 Murray N., Ménard B., Thompson T. A., 2011, *ApJ*, 735, 66
 Naab T. et al., 2014, *MNRAS*, 444, 3357
 Navarro J. F., Frenk C. S., White S. D. M., 1996, *ApJ*, 462, 563
 Nelson D., Genel S., Vogelsberger M., Springel V., Sijacki D., Torrey P., Hernquist L., 2015, *MNRAS*, 448, 59
 Nestor D. B., Johnson B. D., Wild V., Ménard B., Turnshek D. A., Rao S., Pettini M., 2011, *MNRAS*, 412, 1559

Oppenheimer B. D., Davé R., Kereš D., Fardal M., Katz N., Kollmeier J. A., Weinberg D. H., 2010, *MNRAS*, 406, 2325

Pereira-Santaella M. et al., 2016, *A&A*, 594, A81

Planck Collaboration et al., 2014, *A&A*, 571, A1

Power C., Robotham A. S. G., 2016, *ApJ*, 825, 31

Power C., Read J. I., Hobbs A., 2014, *MNRAS*, 440, 3243

Renzini A., Peng Y.-j., 2015, *ApJ*, 801, L29

Rosdahl J., Schaye J., Teyssier R., Agertz O., 2015, *MNRAS*, 451, 34

Rubin K. H. R., Prochaska J. X., Koo D. C., Phillips A. C., Martin C. L., Winstrom L. O., 2014, *ApJ*, 794, 156

Ruszkowski M., Yang H.-Y. K., Zweibel E., 2017, *ApJ*, 834, 208

Salem M., Bryan G. L., 2014, *MNRAS*, 437, 3312

Salpeter E. E., 1955, *ApJ*, 121, 161

Sánchez S. F. et al., 2012, *A&A*, 538, A8

Sarzi M., Kaviraj S., Nedelchev B., Tiffany J., Shabala S. S., Deller A. T., Middelberg E., 2016, *MNRAS*, 456, L25

Scannapieco E., Brüggén M., 2015, *ApJ*, 805, 158

Schaller M., Dalla Vecchia C., Schaye J., Bower R. G., Theuns T., Crain R. A., Furlong M., McCarthy I. G., 2015, *MNRAS*, 454, 2277

Schaye J., Dalla Vecchia C., 2008, *MNRAS*, 383, 1210

Schaye J. et al., 2015, *MNRAS*, 446, 521

Schneider E. E., Robertson B. E., 2017, *ApJ*, 834, 144

Shapley A. E., 2011, *ARA&A*, 49, 525

Sharma M., Theuns T., Frenk C., Bower R. G., Crain R. A., Schaller M., Schaye J., 2017, *MNRAS*, 468, 2176

Sharp R. G., Bland-Hawthorn J., 2010, *ApJ*, 711, 818

Sharp R. et al., 2006, in McLean I. S., Iye M., eds, *Proc. SPIE Conf. Ser. Vol. 6269, Ground-based and Airborne Instrumentation for Astronomy*. SPIE, Bellingham, p. 62690G

Sharp R. et al., 2015, *MNRAS*, 446, 1551

Somerville R. S., Davé R., 2015, *ARA&A*, 53, 51

Springel V., 2005, *MNRAS*, 364, 1105

Springel V., Hernquist L., 2003, *MNRAS*, 339, 289

Springel V., White S. D. M., Tormen G., Kauffmann G., 2001, *MNRAS*, 328, 726

Steidel C. C., Erb D. K., Shapley A. E., Pettini M., Reddy N., Bogosavljević M., Rudie G. C., Rakic O., 2010, *ApJ*, 717, 289

Tanner R., Cecil G., Heitsch F., 2016, *ApJ*, 821, 7

Tanner R., Cecil G., Heitsch F., 2017, *ApJ*, 843, 137

Tescari E., Katsianis A., Wyithe J. S. B., Dolag K., Tornatore L., Barai P., Viel M., Borgani S., 2014, *MNRAS*, 438, 3490

Thompson T. A., Quataert E., Zhang D., Weinberg D. H., 2016, *MNRAS*, 455, 1830

Trayford J. W. et al., 2015, *MNRAS*, 452, 2879

Turner M. L., Schaye J., Crain R. A., Theuns T., Wendt M., 2016, *MNRAS*, 462, 2440

Veilleux S., Cecil G., Bland-Hawthorn J., 2005, *ARA&A*, 43, 769

Wiener J., Pfrommer C., Oh S. P., 2017, *MNRAS*, 467, 906

Wiersma R. P. C., Schaye J., Smith B. D., 2009a, *MNRAS*, 393, 99

Wiersma R. P. C., Schaye J., Theuns T., Dalla Vecchia C., Tornatore L., 2009b, *MNRAS*, 399, 574

Zhang D., Davis S. W., 2017, *ApJ*, 839, 54

Zhang D., Thompson T. A., Quataert E., Murray N., 2017, *MNRAS*, 468, 4801

Zhu G. B. et al., 2015, *ApJ*, 815, 48

APPENDIX A: VARIATIONS OF CUBE SIZE AND GRID RESOLUTION

Our galactic cubelets have a linear dimension of 30 kpc and the pixel size of the velocity dispersion maps is 2 kpc. In this appendix, we investigate the effect of different cube sizes and grid resolutions on our analysis. The result is shown in Fig. A1. Black circles and solid line represent the pixelated velocity dispersion distribution for the fiducial choice of parameters mentioned above (we consider all gas in the edge-on xz projection $-\sigma_y$).

To obtain the distribution described by the orange squares and triple dot-dashed line, we kept fixed the cube size to 30 kpc and




Figure A1. Pixelated velocity dispersion probability distribution (cf. Fig. 3 and the beginning of Section 3.1) of galaxies: resolution tests. Black circles and solid line: fiducial model with cube size = 30 kpc and pixel size = 2 kpc. Orange squares and triple dot-dashed line: cube size = 30 kpc, pixel size = 3 kpc. Blue inverted triangles and dot-dashed line: cube size = 60 kpc, pixel size = 2 kpc. Errors are Poissonian. We consider all gas in the edge-on xz projection $-\sigma_y$. Decreasing the resolution of the grid does not affect the σ -distribution, while changing the cube size from 30 to 60 kpc reduces the statistical relevance of the high- σ tail.

increased the pixel size to 3 kpc. From Fig. A1, it is clear that the decrement in grid resolution does not affect much the new σ -distribution, which is essentially a smoothed version of the fiducial model.

On the other hand, changing the cube size from 30 to 60 kpc (while keeping the grid resolution fixed to 2 kpc) has a large impact (blue inverted triangles and dot-dashed line). The new velocity dispersion distribution has a similar low- σ part as the previous two, but declines more rapidly at $\sigma_y > 70 \text{ km s}^{-1}$. This is due to the fact that the larger cubes include gas in the outskirts of galaxies, where the velocity dispersion is generally small. The additional pixels contribute mostly to the low- σ part, while the increased total number of bins reduces the statistical relevance of the high- σ tail.

APPENDIX B: TESTING THE METHODOLOGY WITH IDEALIZED SIMULATIONS OF DISC GALAXIES

Throughout this work, we have analysed galaxies extracted from one particular run of the EAGLE simulations: *Recal-L025N0752*. As discussed in Section 2.2, the L025N0752 configuration has the highest resolution of the set, and therefore comes in only two slightly different set-ups: *Ref* and *Recal*. Fully exploring the parameter space around the fiducial model would have been numerically too demanding, and was done instead using configurations with lower resolution (L050N0752 and L025N0376, see Crain et al. 2015). Consequently, we have not been able to study the impact of variations in the feedback strength, which are important for interpreting real data and also validating our previous results.

For this reason, we ran four simulations of an isolated disc galaxy. We used a different version of the GADGET-3 code that includes SPH

Table B1. Run name, feedback factor f_f (that regulates the amount of thermal energy injected by SNe into nearby gas particles) and gas maximum velocity dispersion σ_y for the edge-on projection of our idealized disc galaxies.

Run factor (f_f)	Feedback (km s ⁻¹)	max(σ_y)
Strong feedback	1.50	738.74
Fiducial model	1.00	786.67
Weak feedback	0.75	1117.06
No feedback	0.00	157.30

with a higher order dissipation switch (SPHS) than classic SPH. The main advantage of SPHS is that it suppresses spurious numerical errors in the calculation of fluid quantities before they can propagate (Hobbs et al. 2013; Power, Read & Hobbs 2014). At temperatures $T_{\text{gas}} \geq 10^4$ K, the gas is assumed to be of primordial composition and cools radiatively following Katz, Weinberg & Hernquist (1996). At $T_{\text{floor}} = 100$ K $\leq T_{\text{gas}} < 10^4$ K, the gas cools following the prescription of Mashchenko, Wadsley & Couchman (2008) for gas of solar abundance. Gas is also prevented from cooling to the point at which the Jeans mass for gravitational collapse becomes unresolved. Gas above a fixed density threshold forms stars with a star formation efficiency of 10 per cent (Power & Robotham 2016). The subgrid model for star formation is calibrated to follow the Kennicutt–Schmidt law (Kennicutt 1998).

The four *constrained* discs are identical in all but the strength of stellar feedback. The latter is quantified by the feedback factor f_f , which simply (linearly) scales the amount of thermal energy deposited by SNe into neighbouring gas particles. To calculate the energy released by SNe at any given time (where only SNe II are considered and $E_{\text{SN}} = 10^{51}$ erg), the code integrates over a Salpeter (1955) IMF in the range of 8–100 M_{\odot} (to determine the number of SNe II) and adopts an approximate main-sequence time of $t_{\text{MS}} \approx 11.8$ Myr. At t_{MS} after the formation of the star particle, the energy injection is implemented as a delta function in time (Hobbs et al. 2013). We varied the feedback factor from zero to

strong feedback ($f_f = 1.50$), the fiducial model being the one with $f_f = 1.00$ (see Table B1). Each galaxy is composed of a (gas + stellar) disc of radius 10 kpc and a stellar bulge embedded in a DM halo (with a NFW – Navarro, Frenk & White 1996 – concentration parameter $c = 10$), sampled with 308 012 total particles (of which $N_{\text{DM}} = 100\,000$). The mass and spatial resolutions are $1.6 \times 10^5 M_{\odot}$ and 0.01 kpc, respectively. All systems rotate (the DM halo spin parameter is 0.04) and have the same total mass $M_{\text{tot}} = 2.57 \times 10^{12} M_{\odot}$. Gas and stellar masses change according to f_f (as well as N_{gas} and N_{\star}), with $\langle M_{\star} \rangle = 7.42 \times 10^{10} M_{\odot}$. We stress that these discs are not meant to faithfully reproduce physical and morphological properties of the EAGLE galaxies previously used. Our main goal here is testing the methodology.

In the first row of Fig. B1, we plot positions of gas particles for each single disc. From left to right, the following runs are shown: no feedback, weak feedback, fiducial model and strong feedback. We consider all gas in the edge-on xz projection. All systems are plotted at the same evolutionary stage of $t \sim 50$ Myr. As expected, the gas disc becomes more and more perturbed and the amount of outflowing material increases when moving from the no feedback to the strong feedback case. This trend is partially visible also in the second row of Fig. B1, where we show the corresponding gas velocity dispersion maps. It is interesting to note how the weak feedback run produces the largest velocity dispersions, $\max(\sigma_y) \approx 1120$ km s⁻¹ (see Table B1). This somewhat counterintuitive result is due to the fact that, compared to the fiducial and strong feedback simulations, only a few gas particles left the disc at the evolutionary stage considered and therefore the weak feedback σ -map is subjected to large statistical fluctuations.

In Fig. B2, the cumulative pixelated velocity dispersion probability distributions of the constrained discs are visible. We consider all gas in the edge-on xz projection – σ_y . The no feedback run quickly saturates to one at $\sigma_y = 150$ km s⁻¹. In this case, only the disc component is present (according to the leftmost panel in the second row of Fig. B1). This σ -distribution is statistically different from the other three. As soon as feedback is introduced, the distributions shift to progressively larger velocity dispersions




Figure B1. First row: positions in physical kpc of gas particles for our constrained disc galaxies. Second row: corresponding gas velocity dispersion maps. From left to right: the first column shows the no feedback run; second column – weak feedback run; third column – fiducial model; fourth column – strong feedback run. In each panel, we consider all gas in the edge-on xz projection – σ_y .




Figure B2. Cumulative fraction of the pixelated velocity dispersion probability distribution (cf. Fig. 3 and the beginning of Section 3.1) for our constrained disc galaxies. Black diamonds and solid line: fiducial model. Red triangles and dashed line: strong feedback. Orange crosses and triple dot-dashed line: weak feedback. Blue squares and long-dashed line: no feedback. The thin grey horizontal line marks the saturation point of each distribution (cumulative fraction = 1). We consider all gas in the edge-on xz projection – σ_y . As soon as feedback is introduced, the distributions shift to larger velocity dispersions.

following the increase in feedback strength. This is particularly visible up to $\sigma_y \sim 400 \text{ km s}^{-1}$, where there is a crossover between the weak feedback (orange crosses and triple dot-dashed line) and the strong feedback (red triangles and dashed line) runs for the reason explained in the previous paragraph.

These trends fully support the low- $\sigma \Leftrightarrow$ disc + high- $\sigma \Leftrightarrow$ outflows correlations emerging from the analysis of EAGLE galaxies presented in the paper. We refrained from calculating the ξ and η_{50} parameters for the constrained discs because the results would be completely dominated by statistical noise/fluctuations.

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.